

IN THE UNITED STATES DISTRICT COURT
FOR THE MIDDLE DISTRICT OF NORTH CAROLINA

UNITED STATES OF AMERICA; THE
STATE OF NORTH CAROLINA; AND
THE COMMONWEALTH OF
VIRGINIA, SECRETARY OF
NATURAL RESOURCES,

Plaintiffs,

v.

DUKE ENERGY CAROLINAS, LLC,

Defendant.

CIVIL ACTION NO. 1:19-cv-00707

CONSENT DECREE

TABLE OF CONTENTS

I.	BACKGROUND.....	1
II.	JURISDICTION AND VENUE	3
III.	PARTIES BOUND	4
IV.	DEFINITIONS	4
V.	STATEMENT OF PURPOSE.....	7
VI.	PAYMENT BY THE SETTLING DEFENDANT	8
VII.	NATURAL RESOURCE RESTORATION PROJECTS	9
VIII.	REPORTING REQUIREMENTS.....	13
IX.	STIPULATED PENALTIES.....	14
X.	FORCE MAJEURE	17
XI.	DISPUTE RESOLUTION	19
XII.	INFORMATION COLLECTION AND RETENTION; ACCESS TO RESTORATION PROJECT PROPERTIES.....	22
XIII.	COVENANTS NOT TO SUE BY PLAINTIFFS	24
XIV.	RESERVATION OF RIGHTS BY PLAINTIFFS.....	25
XV.	COVENANTS BY THE SETTLING DEFENDANT	27
XVI.	EFFECT OF SETTLEMENT/CONTRIBUTION PROTECTION	29
XVII.	NOTICES	31
XVIII.	APPENDICES	33
XIX.	EFFECTIVE DATE AND RETENTION OF JURISDICTION	33
XX.	CONSENT DECREE MODIFICATIONS	34

XXI.	CONSENT DECREE TERMINATION	34
XXII.	LODGING AND OPPORTUNITY FOR PUBLIC COMMENT	35
XXIII.	SIGNATORIES/SERVICE	35
XXIV.	FINAL JUDGMENT.....	36

I. BACKGROUND

A. Plaintiffs—the United States of America (“United States”), on behalf of the Secretary of the United States Department of the Interior (“DOI”), through the United States Fish and Wildlife Service; the State of North Carolina, through the North Carolina Department of Environmental Quality (“North Carolina”); and the Commonwealth of Virginia, through its Secretary of Natural Resources and the Virginia Department of Environmental Quality (“Virginia”) (collectively, “Plaintiffs”)—filed a Complaint in this action pursuant to Section 107 of the Comprehensive Environmental Response, Compensation, and Liability Act of 1980, as amended, (“CERCLA”), 42 U.S.C. § 9607.

B. Plaintiffs’ Complaint alleges that Defendant Duke Energy Carolinas, LLC (“Settling Defendant”), which has entered into this Consent Decree, is liable under CERCLA for damages for injury to, destruction of, or loss of natural resources, including the reasonable costs of assessing such injury, destruction, or loss, resulting from the releases of hazardous constituents of coal ash when liquefied coal ash was released into the Dan River on February 2, 2014, at and from the Dan River Steam Station (the “Facility”) near Eden, Rockingham County, North Carolina.

C. Pursuant to Executive Order 12580 and the National Contingency Plan, 40 C.F.R. Part 300, DOI, through the United States Fish and Wildlife Service (“FWS”), has been delegated authority to act as Federal Trustee for natural resources impacted by the Release, as that term is defined in Subparagraph 4(l).

D. The North Carolina Department of Environmental Quality has been delegated authority to act as a State Trustee for natural resources in North Carolina impacted by the Release.

E. The Virginia Department of Environmental Quality, acting on behalf of the Secretary of Natural Resources of the Commonwealth of Virginia, has been delegated

authority to act on behalf of the State Trustee for natural resources in Virginia impacted by the Release.

F. The Federal Trustee and the State Trustees (collectively, the “Trustees”) have formed a Trustee Council to coordinate natural resource damage assessment and restoration activities relating to the Release.

G. The Trustees’ natural resource damage assessment activities included reviewing data from the Release response efforts to assess injuries to natural resources located at the Facility and downstream of the Facility where the coal ash came to be located, preparing a natural resource damage assessment plan, soliciting input from the public and interested stakeholders on the scoping document for restoration planning, and considering restoration project proposals submitted by the public.

H. Based upon information developed and analyzed by the Trustees, the damage assessment activities, regulatory standards, and scientific literature, the Trustees used an estimate of the amount of injury to natural resources and their services alleged to have occurred as a result of the Release. The Trustees also used an assessment of lost services of natural resources (e.g., benthic invertebrates, fish, etc.) that could occur as a consequence of the Release, including exposure to high concentrations of hazardous substances arsenic and selenium in surface water and/or sediment.

I. The Trustees relied on two decision support models (an ecological service model and a human-use services model) to determine the type and magnitude of restoration required to restore the injured natural resources and their services identified by the Trustees’ assessment.

J. The Trustees have prepared a draft Restoration Plan in accordance with 42 U.S.C. § 9611 and 43 C.F.R. § 11.93 to evaluate and select proposed restoration alternatives that will restore, rehabilitate, replace, and/or acquire natural resources and services equivalent to those allegedly injured, lost, or destroyed as a result of the Release.

A copy of the draft Restoration Plan is attached as Appendix B to this Consent Decree. The Trustees' final Restoration Plan shall accompany any motion filed with the Court to enter this Consent Decree.

K. To date, the Settling Defendant has paid at least \$557,023.31 to DOI, \$77,884.81 to North Carolina, and \$726,145.49 to Virginia as reimbursement for costs incurred in connection with the Release since the Release and prior to the date of lodging of this Consent Decree.

L. By entry into this Consent Decree, the Settling Defendant does not admit any liability to the Plaintiffs arising out of the transactions or occurrences alleged in the Complaint.

M. The Parties to this Consent Decree recognize, and the Court by entering this Consent Decree finds, that this Consent Decree: (i) has been negotiated by the Parties in good faith; (ii) will avoid prolonged and complicated litigation among the Parties; (iii) will expedite the restoration of natural resources allegedly injured at and near the Dan River, including restoration activities performed, and to be performed, by the Settling Defendant; and (iv) is fair, reasonable, and in the public interest.

N. The Settling Defendant agrees that this Consent Decree is outside the scope of the settlement agreement entered into by the Settling Defendant and the North Carolina Department of Environmental Quality on September 23, 2016 ("2016 NC Settlement Agreement") and the Settling Defendant will not attempt to use the 2016 NC Settlement Agreement as a basis for challenging any provision of this Consent Decree.

NOW, THEREFORE, it is hereby ORDERED, ADJUDGED, AND DECREED:

II. JURISDICTION AND VENUE

1. This Court has jurisdiction over the subject matter of this action pursuant to Sections 107 and 113(b) of CERCLA, 42 U.S.C. §§ 9607 and 9613(b); and 28 U.S.C. §§ 1331 and 1345. The Court also has personal jurisdiction over the Settling Defendant.

Venue lies in the Middle District of North Carolina pursuant to Section 113(b) of CERCLA, 42 U.S.C. § 9613(b), and 28 U.S.C. §§ 1391(b) and (c), because the Release alleged in the Complaint occurred in, and the Settling Defendant resides in, this judicial district. Solely for the purposes of this Consent Decree and the underlying Complaint, the Settling Defendant waives all objections and defenses that it may have to jurisdiction of the Court or to venue in this District. The Settling Defendant shall not challenge the terms of this Consent Decree or this Court's jurisdiction to enter and enforce this Consent Decree.

III. PARTIES BOUND

2. This Consent Decree applies to and is binding upon the Plaintiffs and upon the Settling Defendant and its successors and assigns. Any change in ownership or corporate status of the Settling Defendant including, but not limited to, any transfer of assets or real or personal property, shall in no way alter the Settling Defendant's responsibilities under this Consent Decree.

3. The Settling Defendant shall be responsible for ensuring that its contractors and subcontractors perform any work required hereunder in accordance with the terms of this Consent Decree. In any action to enforce this Consent Decree, the Settling Defendant shall not raise as a defense the failure by any of its officers, directors, employees, agents, or contractors to take any actions necessary to comply with the provisions of this Consent Decree.

IV. DEFINITIONS

4. Unless otherwise expressly provided herein, terms used in this Consent Decree that are defined in CERCLA, the Clean Water Act ("CWA"), 33 U.S.C. § 1251 et seq., or in regulations promulgated under CERCLA or the CWA, shall have the meaning assigned to them in such law or regulations. Whenever terms listed below are used in

this Consent Decree or in the appendices attached hereto and incorporated hereunder, the following definitions shall apply:

a. “Consent Decree” or “Decree” means this Consent Decree and all appendices attached hereto (listed in Section XVIII (Appendices)). In the event of conflict between this Consent Decree and any appendix, this Consent Decree shall control.

b. “Day” means a calendar day unless expressly stated to be a working day. “Working day” shall mean a day other than a Saturday, Sunday, or Federal holiday. In computing any period of time under this Consent Decree, where the last day would fall on a Saturday, Sunday, or Federal holiday, the period shall run until the close of business of the next working day.

c. “DOI” means the United States Department of the Interior and any successor departments or agencies of the United States.

d. “Effective Date” means the effective date of this Consent Decree as provided by Section XIX of this Consent Decree (Effective Date and Retention of Jurisdiction).

e. “Interest” means interest at the rate specified for interest on investments of the EPA Hazardous Substance Superfund established by 26 U.S.C. § 9507, compounded annually on October 1 of each year, in accordance with 42 U.S.C. § 9607(a). The applicable rate of interest shall be the rate in effect at the time the interest accrues. The rate of interest is subject to change on October 1 of each year.

f. “Natural Resource” or “Natural Resources” means land, fish, wildlife, biota, air, water, ground water, drinking water supplies, and other such resources, belonging to, managed by, held in trust by, appertaining to, or otherwise controlled by the United States and/or the States.

g. “Natural Resource Damages” means any damages recoverable by

the United States or the States on behalf of the public for injury to, destruction of, loss of, loss of use of, or impairment of Natural Resources as a result of the Release, including, but not limited to: (i) the reasonable costs of assessing injury to, destruction of, loss of, or impairment of Natural Resources; (ii) the costs of restoration, rehabilitation, or replacement of injured or lost Natural Resources or of acquisition of equivalent resources and/or their services; (iii) compensation for injury, destruction, loss, loss of use, diminution in value, or impairment of Natural Resources; (iv) the costs of planning, implementing, and monitoring restoration activities; and (v) each of the categories of recoverable damages described in 43 C.F.R. § 11.15 and applicable state law.

h. “NRDAR Fund” means DOI’s Natural Resource Damage Assessment and Restoration Fund.

i. “Paragraph” means a portion of this Consent Decree identified by an arabic numeral or an upper case letter.

j. “Parties” means the United States, the States, and the Settling Defendant.

k. “Plaintiffs” means the United States and the States.

l. “Release” means the release of liquefied coal ash into the Dan River on February 2, 2014, at and from the Duke Energy Dan River Steam Station (owned and operated by the Settling Defendant) near Eden, Rockingham County, North Carolina downstream to the John H. Kerr reservoir in Mecklenburg County, Virginia. *See* Appendix A.

m. “Restoration Projects” means those aquatic, terrestrial, and human-use restoration projects performed and to be performed by the Settling Defendant as described in Section VII of this Consent Decree (Natural Resource Restoration Projects).

n. “RIM Costs” means the natural resource restoration planning,

implementation and monitoring costs to be incurred by the Trustees in connection with the Release, including costs to oversee compliance with, and to implement, this Consent Decree and costs to implement, and to amend if necessary, the Restoration Plan for the Dan River Coal Ash Spill prepared by the Trustee Council.

o. “Section” means a portion of this Consent Decree identified by a roman numeral.

p. “Settling Defendant” means Duke Energy Carolinas, LLC.

q. “State” or “States” means the State of North Carolina and the Commonwealth of Virginia, individually or collectively, together with agencies and instrumentalities thereof.

r. “Subparagraph” means a portion of this Consent Decree identified by a lower case letter.

s. “Trustees” means DOI, acting through the United States Fish and Wildlife Service; the State of North Carolina, acting through the North Carolina Department of Environmental Quality; and the Commonwealth of Virginia, acting through its Secretary of Natural Resources.

t. “United States” means the United States of America, including all of its departments, agencies, and instrumentalities.

V. STATEMENT OF PURPOSE

5. The mutual objectives of the Parties in entering into this Consent Decree are: (i) to contribute to the restoration, replacement, or acquisition of the equivalent of the Natural Resources allegedly injured, destroyed, or lost as a result of hazardous substances released during the Release; (ii) to fund the Trustees’ future natural resource restoration planning, implementation, and monitoring costs; (iii) to resolve the Settling Defendant’s liability for Natural Resource Damages as provided herein; and (iv) to avoid potentially costly and time-consuming litigation.

VI. PAYMENT BY THE SETTLING DEFENDANT

6. Payment for DOI'S RIM Costs. Within 30 days after the Effective Date, the Settling Defendant shall pay a total of \$39,215 for DOI's RIM Costs to be incurred after the Effective Date of this Consent Decree. The Settling Defendant shall pay the amount due by FedWire Electronic Funds Transfer ("EFT") to the U.S. Department of Justice account, in accordance with written instructions provided to the Settling Defendant by the Financial Litigation Unit ("FLU") of the United States Attorney's Office for the Middle District of North Carolina after the Effective Date. The payment instructions provided by the FLU will include a Consolidated Debt Collection System ("CDCS") number, which the Settling Defendant shall use to identify all payments required to be made in accordance with this Consent Decree. The FLU will provide payment instructions to:

Patti Ross
DEC45A 550 South Tryon Street
Charlotte, North Carolina 28202
(704) 382-8147
patti.ross@duke-energy.com

on behalf of the Settling Defendant. The Settling Defendant may change the individual to receive payment instructions on its behalf by providing written notice of such change to the United States in accordance with Section XVII (Notices). At the time of payment, the Settling Defendant shall send notice to the United States in accordance with Section XVII that payment has been made. Such notice shall reference the civil action number, CDCS number, and DOJ case number 90-5-1-1-11057/2. The total amount paid shall be deposited in a segregated sub-account within the NRDAR Fund, to be managed by DOI and applied toward RIM Costs incurred by DOI.

7. Payment for North Carolina's RIM Costs. Within 30 days after the

Effective Date, the Settling Defendant shall pay a total of \$18,095 for North Carolina's RIM Costs to be incurred after the Effective Date of this Consent Decree. The Settling Defendant shall pay the amount due by check payable to the North Carolina Department of Environmental Quality, Financial Services Division, mailed to:

North Carolina Department of Environmental Quality
Financial Services Division
1606 Mail Service Center
Raleigh, North Carolina 27699-1606

At the time of payment, the Settling Defendant shall send notice to North Carolina in accordance with Section XVII that payment has been made. Such notice shall reference the civil action number.

VII. NATURAL RESOURCE RESTORATION PROJECTS

8. The Settling Defendant has completed the following Restoration Projects:
 - a. Pigg River Power Dam Partial Removal: The Settling Defendant funded removal of the defunct Power Dam on the Pigg River located in Franklin County, Virginia. Constructed in 1915 for power generation, Power Dam measured 25 feet by 204 feet long and impounded 60 acre-feet of water over 25 acres. Power Dam was the last impediment to fish passage within a 72-mile reach of the Pigg River from the headwaters downstream to Leesville Reservoir. Removal of the dam increased aquatic ecological services for fish and benthic invertebrates. It also restored 2.2 miles of aquatic instream habitat impounded upstream of the dam for smallmouth bass and the federally and state-listed endangered Roanoke logperch. The project improved instream habitat, vegetation, and competency to transport sediment another mile upstream and five miles downstream of the dam. It also enhanced the channel habitat, stability, and complexity of the remaining 45-mile Pigg River segment to the Leesville Reservoir.

- b. Abreu-Grogan Park Improvements: The Settling Defendant made

improvements to the three-acre Abreu-Grogan Park in Danville, Virginia, which was closed for several months while coal ash was dredged from the Dan River as a result of the Release. The improvements include a boat dock for launching and retrieving boats, a handicap-accessible restroom, fishing platform, sidewalks, and an information kiosk.

c. Mayo River Land Conservation: The Settling Defendant funded the acquisition of 340 acres of real property along the Mayo River in North Carolina, including 3 miles of river corridor, and title was transferred to North Carolina for long-term stewardship and conservation in perpetuity as part of North Carolina's Mayo River State Park. The Settling Defendant also funded the acquisition of 214 acres of real property along the Mayo River in Henry County, Virginia, and title was transferred to Virginia for long-term stewardship and conservation in perpetuity as part of Virginia's Mayo River State Park. Acquisition of these lands and transfer to the respective state park systems of North Carolina and Virginia allow long-term recreational improvements to be implemented. Conservation of these portions of river corridor also protects significant aquatic habitat with at least 10 rare and listed aquatic species and adjacent terrestrial natural heritage features. These additions to the state park systems allow greater access and safety for the public to experience river-based recreation and fishing, as well as camping, hiking, and environmental education.

9. Additional Restoration Projects. The Settling Defendant shall finance and complete the Restoration Projects described in Appendix C (Restoration Project Scopes of Work): (i) Additional Mayo River Land Conservation and (ii) Public Boat Access. All restoration work performed by the Settling Defendant shall be in accordance with the Trustees' final Restoration Plan and any amendments thereto. To the extent required to implement a Restoration Project, the Settling Defendant's acquisition of real property and conveyance of such property to a State is subject to Paragraphs 10 through 12.

10. Acquisition of Properties. Within 18 months after the Effective Date, or

within such other time period if agreed to in writing by the Trustees, the Settling Defendant shall acquire, or cause to be acquired on its behalf, fee simple title to real property meeting the Performance Criteria in the applicable Scope of Work (Appendix C). Prior to acquiring title, the Settling Defendant shall satisfy any requirements of the State receiving title and shall document how such requirements are satisfied for each parcel to be acquired. All costs of acquisition (including due diligence and closing costs) shall be borne by the Settling Defendant.

11. Conveyance of Properties. In conveying ownership of any real property to a State, the Settling Defendant shall cooperate with any closing requirements provided in writing by a State or required under State law. Within 14 days of a State's written request to the Settling Defendant, or within such other time period if agreed to in writing by the Trustees, the Settling Defendant shall execute and deliver to the satisfaction of the receiving State a deed conveying fee simple title to the property free and clear of all liens and encumbrances except as otherwise agreed to by the State that, in the State's sole discretion, will not interfere with the compensatory purpose and intended use of the property. All costs of conveyance (including transfer costs and closing costs) shall be borne by the Settling Defendant. Within seven days of any conveyance to a State, the Settling Defendant shall notify the Trustees that the conveyance has occurred.

12. Contingency for Property Acquisition. In the event that the Settling Defendant, or its agent, fails to obtain the requisite title from a third party, as provided in Paragraph 10, necessary to implement a Restoration Project due to a force majeure event or an inability to acquire title at a commercially reasonable price, the Trustees may direct the Settling Defendant to instead acquire an alternate property (or combination of properties) that achieves comparable ecological function, recreation opportunity, and/or location as the original Restoration Project, taking into account any ecological or recreational benefits that have been or will be achieved from any portion(s) of the

original Restoration Project that may have been completed. The Settling Defendant shall implement the project at the alternate property within a mutually agreed upon timeframe. If the Settling Defendant seeks to assert either a force majeure event or an inability to acquire title at a commercially reasonable price with respect to any property addressed by this Paragraph, then the Settling Defendant shall comply in the first instance with the notice requirement and all other requirements set forth in the provisions of Section X (Force Majeure).

13. Conservation of Properties and Maintenance of Boat Access Locations.

With regard to any Restoration Project, the State shall conserve and manage such Restoration Project consistently with the Restoration Project's function and purpose to compensate the public for alleged injuries and losses of Natural Resources and/or their services pursuant to this Consent Decree and as set forth in the Scopes of Work (Appendix C).

14. Construction of Public Boat Access Facility in North Carolina, If Applicable. If, under the Public Boat Access Restoration Project described in Appendix C (Restoration Project Scopes of Work), the identified boat access location(s) is in North Carolina, the Settling Defendant shall construct a boat access facility at such location(s), using designs approved by the North Carolina Wildlife Resources Commission, and (if applicable) convey the property to North Carolina after construction is complete. The Settling Defendant shall complete construction of the boat access facility within one year of receiving design plan approvals from the North Carolina Wildlife Resources Commission, and the Settling Defendant shall notify the Trustees in writing within 7 days of completing construction of a facility.

15. Construction of Public Boat Access Facility in Virginia, If Applicable. If, under the Public Boat Access Restoration Project described in Appendix C (Restoration Project Scopes of Work), the identified boat access location(s) is in Virginia, the Settling

Defendant shall construct a boat access facility at such location(s), using designs approved by the Virginia Department of Game and Inland Fisheries, and (if applicable) convey the property to Virginia after construction is complete. The Settling Defendant shall complete construction of the boat access facility within one year of receiving design plan approvals from the Virginia Department of Game and Inland Fisheries, and the Settling Defendant shall notify the Trustees in writing within 7 days of completing construction of a facility.

VIII. REPORTING REQUIREMENTS

16. Beginning no sooner than six months after the lodging of this Consent Decree, and until termination of this Decree pursuant to Section XXI, the Settling Defendant shall submit by email to the Plaintiffs a semi-annual report on January 31st and July 31st of each year for the preceding half-calendar-year (i.e., July 1st through December 31st and January 1st through June 30th, respectively). For the first semi-annual report only, the reporting period shall commence with the lodging of this Consent Decree and extend through June 30, 2019. Each semi-annual report shall summarize the status of the Settling Defendant's progress in satisfying its obligations under Paragraph 9 (Additional Restoration Projects), including, at a minimum, (i) a narrative description of relevant activities undertaken and any problems encountered and solutions implemented during the reporting period, (ii) a narrative description of any anticipated problems and proposed solutions to such problems, (iii) appropriate maps and photographs demonstrating the Settling Defendant's progress, and (iv) a narrative description, including a schedule if applicable, of anticipated activities to be undertaken in the next reporting period in furtherance of its obligations under Paragraph 9.

17. Each report submitted by the Settling Defendant under this Section shall be signed by an official of the submitting party and include the following certification:

I certify under penalty of law that this document and all attachments were

prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I have no personal knowledge that the information submitted is other than true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

18. Any information provided pursuant to this Consent Decree may be used by the Plaintiffs in any proceeding to enforce the provisions of this Consent Decree and as otherwise permitted by law.

19. The reporting requirements of this Consent Decree do not relieve the Settling Defendant of any reporting obligations required by CERCLA, the CWA, the SWCL, or their respective implementing regulations, or by any other federal, state, or local law, regulation, permit, or other requirement.

IX. STIPULATED PENALTIES

20. The Settling Defendant shall be liable for stipulated penalties to the United States and the States for violations of this Consent Decree as specified below, unless excused under Section X (Force Majeure). A violation includes failing to perform any obligation required by the terms of this Decree, including any Restoration Project or schedule approved under this Decree, according to all applicable requirements of this Decree and within the specified time schedules established by or approved under this Decree.

21. The Settling Defendant shall not deduct any penalties paid under this Decree pursuant to this Section in calculating its federal, State, or local income tax.

22. Payment Obligation.

a. Interest. In the event any payment required by Paragraph 6 is not made when due, the Settling Defendant shall pay Interest on the unpaid balance

commencing on the payment due date and accruing through the date of full payment.

b. Stipulated Penalties. In addition to the Interest required to be paid under the preceding Subparagraph, if any payment required by Section VI (Payment by Settling Defendant) is not made when due, the Settling Defendant shall also pay the following stipulated penalties per day for each day that the payment is late through the date of full payment.

Period of Noncompliance	Penalty Per Violation Per Day
1st through 14th day	\$500
15th through 30th day	\$1,000
31st day and beyond	\$3,000

23. Restoration Project Requirements. The following stipulated penalties shall accrue per violation per day for each failure to satisfy any requirement or deadline (excluding notice requirements) set forth in Section VII (Natural Resource Restoration Projects).

Period of Noncompliance	Penalty Per Violation Per Day
1st through 30th day	\$1,250
31st day and beyond	\$3,000

24. Reporting and Notice Requirements. The following stipulated penalties shall accrue per violation per day for each violation of the requirements of Section VIII (Reporting Requirements) and the notice requirements set forth in Paragraphs 11, 12, 14, and 15 of Section VII (Natural Resource Restoration Projects).

Period of Noncompliance	Penalty Per Violation Per Day
1st through 30th day	\$750
31st day and beyond	\$2,000

25. Stipulated penalties under this Section shall begin to accrue on the day after performance is due or on the day a violation occurs, whichever is applicable, and shall

continue to accrue until performance is satisfactorily completed or until the violation ceases. Stipulated penalties shall accrue simultaneously for separate violations of this Decree.

26. The Settling Defendant shall pay any stipulated penalties to the United States and the States within 30 days of a written demand by any Plaintiff. Of the total stipulated penalty amount due, the Settling Defendant shall pay 33.4% percent to the United States, 33.3% to North Carolina, and 33.3% to Virginia. The Plaintiff making a demand for payment of a stipulated penalty shall simultaneously send a copy of the demand to the other Plaintiffs.

27. Any Interest payments under Subparagraph 22(a) shall be paid in the same manner as the overdue principal amount, and shall be directed to the same account as the overdue principal amount. Any stipulated penalties payments to the United States under this Section IX shall be paid in accordance with Paragraph 6 above, and shall be deposited in the United States Treasury.

28. Any Plaintiff may, in the unreviewable exercise of its discretion, reduce or waive stipulated penalties otherwise due it under this Consent Decree.

29. Stipulated penalties shall continue to accrue as provided in Paragraph 25, during any Dispute Resolution, but need not be paid until the following:

a. If the dispute is resolved by agreement of the Parties or by a decision of the Plaintiffs that is not appealed to the Court, the Settling Defendant shall pay accrued penalties determined to be owing, together with Interest, to the Plaintiffs within 30 days of the effective date of the agreement or the receipt of the Plaintiffs' decision.

b. If the dispute is appealed to the Court and the Plaintiffs prevail in whole or in part, the Settling Defendant shall pay all accrued penalties determined by the Court to be owing, together with Interest, within 60 days of receiving the Court's decision or order, except as provided in Subparagraph c, below.

c. If any Party appeals the District Court's decision, the Settling Defendant shall pay all accrued penalties determined to be owing, together with Interest, within 15 Days of receiving the final appellate court decision.

30. If the Settling Defendant fails to pay stipulated penalties according to the terms of this Consent Decree, the Settling Defendant shall be liable for Interest on such penalties, accruing as of the date payment became due. Nothing in this Paragraph shall be construed to limit the United States or the States from seeking any remedy otherwise provided by law for the Settling Defendant's failure to pay any stipulated penalties.

31. The payment of penalties and interest, if any, shall not alter in any way the Settling Defendant's obligation to complete the performance of the requirements of this Consent Decree.

32. Non-Exclusivity of Remedy. Stipulated penalties are not the United States' or the States' exclusive remedy for violations of this Consent Decree. Subject to the provisions of Sections XIV and XVI (Reservation of Rights by Plaintiffs and Effect of Settlement/Contribution Protection), the Plaintiffs expressly reserve the right to seek any other relief that a Plaintiff deems appropriate for the Settling Defendant's violation of this Decree or applicable law, including but not limited to an action against the Settling Defendant for statutory penalties, additional injunctive relief or restoration work, and/or contempt. However, the amount of any statutory penalty assessed for a violation of this Consent Decree shall be reduced by an amount equal to the amount of any stipulated penalty assessed and paid pursuant to this Consent Decree.

X. FORCE MAJEURE

33. "Force majeure," for purposes of this Consent Decree, is defined as any event arising from causes beyond the control of the Settling Defendant, of any entity controlled by the Settling Defendant, or of the Settling Defendant's contractors, that delays or prevents the performance of any obligation under this Consent Decree despite

the Settling Defendant's best efforts to fulfill the obligation. The requirement that Defendant exercise "best efforts to fulfill the obligation" includes using best efforts to anticipate any potential force majeure event and best efforts to address the effects of any potential force majeure event (a) as it is occurring and (b) following the potential force majeure, such that the delay and any adverse effects of the delay are minimized. "Force majeure" does not include the Settling Defendant's financial inability to perform any obligation under this Consent Decree.

34. If any event occurs or has occurred that may delay the performance of any obligation under this Consent Decree, whether or not caused by a force majeure event, the Settling Defendant shall provide notice by email to the Trustees, within seven days of when the Settling Defendant first knew that the event may cause a delay. Within seven days thereafter, the Settling Defendant shall provide in writing to the Trustees an explanation and description of the reasons for the delay; the anticipated duration of the delay; all actions taken or to be taken to prevent or minimize the delay; a schedule for implementation of any measures to be taken to prevent or mitigate the delay or the effect of the delay; the Settling Defendant's rationale for attributing such delay to a force majeure event if it intends to assert such a claim; and a statement as to whether, in the opinion of the Settling Defendant, such event may cause or contribute to an endangerment to public health, welfare or the environment. The Settling Defendant shall include with any notice all available documentation supporting the claim that the delay was attributable to a force majeure. Failure to comply with the above requirements shall preclude the Settling Defendant from asserting any claim of force majeure for that event for the period of time of such failure to comply, and for any additional delay caused by such failure. The Settling Defendant shall be deemed to know of any circumstance of which the Settling Defendant, any entity controlled by the Settling Defendant, or the Settling Defendant's contractors knew or should have known.

35. If the Trustees agree that the delay or anticipated delay is attributable to a force majeure event, the time for performance of the obligations under this Consent Decree that are affected by the force majeure event will be extended by the Trustees for such time as is necessary to complete those obligations. An extension of the time for performance of the obligations affected by the force majeure event shall not, of itself, extend the time for performance of any other obligation. The Trustees will notify the Settling Defendant in writing of the length of the extension, if any, for performance of the obligations affected by the force majeure event.

36. If the Trustees do not agree that the delay or anticipated delay has been or will be caused by a force majeure event, the Trustees will notify the Settling Defendant in writing of their decision.

37. If the Settling Defendant elects to invoke the dispute resolution procedures set forth in Section XI (Dispute Resolution), it shall do so no later than 15 days after receipt of the Trustees' notice. In any such proceeding, the Settling Defendant shall have the burden of demonstrating by a preponderance of the evidence that the delay or anticipated delay has been or will be caused by a force majeure event, that the duration of the delay or the extension sought was or will be warranted under the circumstances, that best efforts were exercised to avoid and mitigate the effects of the delay, and that the Settling Defendant complied with the requirements of Paragraphs 33 and 34. If the Settling Defendant carries this burden, the delay at issue shall be deemed not to be a violation by the Settling Defendant of the affected obligation of this Consent Decree identified to the Trustees and the Court.

XI. DISPUTE RESOLUTION

38. Unless otherwise expressly provided for in this Consent Decree, the dispute resolution procedures of this Section shall be the exclusive mechanism to resolve disputes arising under or with respect to this Consent Decree.

39. Informal Dispute Resolution. Any dispute subject to Dispute Resolution under this Consent Decree shall first be the subject of informal negotiations. The dispute shall be considered to have arisen when the Settling Defendant sends the Plaintiffs a written Notice of Dispute. Such Notice of Dispute shall state clearly the matter in dispute. The period of informal negotiations shall not exceed 30 days from the date the dispute arises, unless that period is modified by written agreement. If the Parties cannot resolve a dispute by informal negotiations, then the position advanced by the Plaintiffs shall be considered binding unless, within 15 days after the conclusion of the informal negotiation period, the Settling Defendant invokes formal dispute resolution procedures as set forth below.

40. Formal Dispute Resolution. The Settling Defendant shall invoke formal dispute resolution procedures, within the time period provided in the preceding Paragraph, by sending the Plaintiffs a written Statement of Position regarding the matter in dispute. The Statement of Position shall include, but need not be limited to, any factual data, analysis, or opinion supporting the Settling Defendant's position and any supporting documentation relied upon by the Settling Defendant.

41. The Plaintiffs shall send their Statement of Position to the Settling Defendant within 60 days of receipt of the Settling Defendant's Statement of Position. The Statement of Position shall include, but need not be limited to, any factual data, analysis, or opinion supporting that position and any supporting documentation relied upon by the Plaintiffs. The Statement of Position shall be binding on the Settling Defendant, unless the Settling Defendant files a motion for judicial review of the dispute in accordance with the following Paragraph.

42. The Settling Defendant may seek judicial review of the dispute by filing with the Court and serving on the Plaintiffs, in accordance with Section XVII (Notices), a motion requesting judicial resolution of the dispute. The motion must be filed within 10

days of receipt of the Plaintiffs' Statement of Position pursuant to the preceding Paragraph. The motion shall contain a written statement of the Settling Defendant's position on the matter in dispute, including any supporting factual data, analysis, opinion, or documentation, and shall set forth the relief requested and any schedule within which the dispute must be resolved for orderly implementation of the Consent Decree.

43. The Plaintiffs shall respond to the Settling Defendant's motion within the time period allowed by the Local Rules of this Court. The Settling Defendant may file a reply memorandum, to the extent permitted by the Local Rules.

44. Standard of Review

a. Disputes Concerning Matters Accorded Record Review. Except as otherwise provided in this Consent Decree, in any dispute brought under Paragraph 40 pertaining to the adequacy or appropriateness of proposed changes to the Restoration Projects described in Paragraph 9, procedures to implement a Restoration Project, schedules, or any other items requiring approval by the Trustees under this Consent Decree; the adequacy of the performance of work undertaken pursuant to this Consent Decree; and all other disputes that are accorded review on the administrative record under applicable principles of administrative law, the Settling Defendant shall have the burden of demonstrating, based on the administrative record, that the position of the Plaintiffs is arbitrary and capricious or otherwise not in accordance with law.

b. Other Disputes. Except as otherwise provided in this Consent Decree, in any other dispute brought under Paragraph 40, the Settling Defendant shall bear the burden of demonstrating that its position complies with this Consent Decree and better furthers the Consent Decree's objective to contribute to the restoration, replacement, or acquisition of the equivalent of the natural resources allegedly injured, destroyed, or lost as a result of the Release.

45. The invocation of dispute resolution procedures under this Section shall

not, by itself, extend, postpone, or affect in any way any obligation of the Settling Defendant under this Consent Decree, unless and until final resolution of the dispute so provides. Stipulated penalties with respect to the disputed matter shall continue to accrue from the first day of noncompliance, but payment shall be stayed pending resolution of the dispute as provided in Paragraph 29. If the Settling Defendant does not prevail on the disputed issue, stipulated penalties shall be assessed and paid as provided in Section IX (Stipulated Penalties).

XII. INFORMATION COLLECTION AND RETENTION; ACCESS TO RESTORATION PROJECT PROPERTIES

46. To the extent that the Settling Defendant has such right of entry, the United States, the States, and their representatives, including attorneys, contractors, and consultants, shall have the right of entry onto any real property that is subject to an uncompleted Restoration Project, or any other real property where access is needed for purposes of this Consent Decree, at all reasonable times, upon presentation of credentials, to:

- a. monitor the progress of activities required under this Consent Decree;
- b. verify any data or information submitted to the United States or a State in accordance with the terms of this Consent Decree;
- c. obtain documentary evidence, including photographs and similar data; and
- d. assess the Settling Defendant's compliance with this Consent Decree.

47. Until five years after the termination of this Consent Decree, the Settling Defendant shall retain, and shall instruct its contractors and agents to preserve, all non-identical copies of all documents, records, or other information (including documents, records, or other information in electronic form) (hereinafter referred to as

“Records”) in its or its contractors’ or agents’ possession or control, or that come into its or its contractors’ or agents’ possession or control, and that relate in any manner to the Settling Defendant’s performance of its obligations under this Consent Decree. This information-retention requirement shall apply regardless of any contrary corporate or institutional policies or procedures. At any time during this information-retention period, upon request by the United States or a State, the Settling Defendant shall provide copies of any Records required to be maintained under this Paragraph.

48. At the conclusion of the information-retention period provided in the preceding Paragraph, the Settling Defendant shall notify the Plaintiffs at least 90 days prior to the destruction of any Records subject to the requirements of the preceding Paragraph and, upon request by any Plaintiff, the Settling Defendant shall deliver any such Records to DOI or the State.

49. Privilege Claims and Business Confidential Claims.

a. The Settling Defendant may assert that a certain Record is privileged under the attorney-client privilege or any other privilege recognized by federal law. If a claim of privilege applies only to a portion of a Record, the Settling Defendant shall provide the Record in redacted form to mask the privileged or protected portion only. If the Settling Defendant asserts such a privilege, it shall provide the following: (a) the title of the document, record, or information; (b) the date of the document, record, or information; (c) the name and title of each author of the document, record, or information; (d) the name and title of each addressee and recipient; (e) a description of the subject of the document, record, or information; and (f) the privilege asserted by the Settling Defendant. The Settling Defendant shall retain all Records claimed to be privileged until the Trustees have had a reasonable opportunity to dispute the privilege claim and any such dispute has been resolved in the Settling Defendant’s favor.

b. The Settling Defendant may also assert that a certain Record is

protected as business confidential to the extent permitted by and in accordance with Section 104(e)(7) of CERCLA, 42 U.S.C. § 9604(e)(7), and 40 C.F.R. § 2.203(b). If the Settling Defendant asserts such protection, the Settling Defendant shall segregate and clearly identify all Records or parts thereof for which the Settling Defendant asserts business confidentiality claims. Records determined to be confidential by the Trustees will be afforded the protection specified in 40 C.F.R. Part 2, Subpart B. If no claim of confidentiality accompanies Records when they are submitted to the Trustees, or if the Trustees have notified the Settling Defendant that the Records are not confidential under the standards of Section 104(e)(7) of CERCLA or 40 C.F.R. Part 2, Subpart B, the public may be given access to such Records without further notice to Settling Defendant.

50. However, no Records created or generated pursuant to the requirements of this Consent Decree, and no data (including but not limited to sampling, analytical, monitoring, hydrogeologic, scientific, chemical, and engineering data) or any other documents or information evidencing conditions caused by the Release, shall be withheld from the Plaintiffs on grounds of privilege or confidentiality.

51. This Consent Decree in no way limits or affects any right of entry and inspection, or any right to obtain information, held by the United States or a State pursuant to applicable federal or state laws, regulations, or permits, nor does it limit or affect any duty or obligation of the Settling Defendant to maintain documents, records, or other information imposed by applicable federal or state laws, regulations, or permits.

XIII. COVENANTS NOT TO SUE BY PLAINTIFFS

52. Covenant by the United States. Except as specifically provided by Paragraph 54 (General Reservations) and Paragraph 55 (Special Reservations Regarding Natural Resource Damages), the United States covenants not to sue or take administrative action against the Settling Defendant for Natural Resource Damages known as of the date of lodging this Consent Decree with the Court pursuant to CERCLA Section 107,

42 U.S.C. § 9607, and the Clean Water Act Section 311, 33 U.S.C. § 1321. This covenant not to sue shall take effect upon receipt of the Settling Defendant's payment pursuant to Section VI (Payment by the Settling Defendant). This covenant not to sue is conditioned upon the satisfactory performance by the Settling Defendant of its obligations under this Consent Decree. This covenant not to sue extends only to the Settling Defendant and does not extend to any other person.

53. Covenant by the States. Except as specifically provided by Paragraph 54 (General Reservations) and Paragraph 55 (Special Reservations Regarding Natural Resource Damages), the States covenant not to sue the Settling Defendant for Natural Resource Damages known as of the date of lodging this Consent Decree with the Court pursuant to CERCLA Section 107, 42 U.S.C. § 9607, the Clean Water Act Section 311, 33 U.S.C. § 1321, and, as to Virginia, the SWCL. This covenant not to sue shall take effect upon receipt of the Settling Defendant's payment pursuant to Section VI (Payment by the Settling Defendant). This covenant not to sue is conditioned upon the satisfactory performance by the Settling Defendant of its obligations under this Consent Decree. This covenant not to sue extends only to the Settling Defendant and does not extend to any other person.

XIV. RESERVATION OF RIGHTS BY PLAINTIFFS

54. General Reservations. The United States and the States reserve, and this Consent Decree is without prejudice to, all rights against the Settling Defendant and with respect to all matters not expressly included within Paragraph 52 (Covenant by the United States) and Paragraph 53 (Covenant by the States). Notwithstanding any other provisions of this Consent Decree, the United States and the States reserve all rights against the Settling Defendant with respect to:

a. claims based on a failure by the Settling Defendant to meet a requirement of this Consent Decree;

b. liability for injunctive relief or administrative order enforcement under CERCLA Section 106, 42 U.S.C. § 9606;

c. liability under CERCLA Section 107(a)(4)(A), 42 U.S.C. § 9607(a)(4)(A), for costs of removal or remedial action incurred by the United States Government or a State or an Indian tribe;

d. liability under CERCLA Section 107(a)(4)(D), 42 U.S.C. § 9607(a)(4)(D), for costs of any health assessment or health effects study carried out under 42 U.S.C. § 9604(i);

e. liability for any other costs incurred or to be incurred by the United States or by a State that are not within the definition of Natural Resource Damages;

f. liability for damages for injury to, destruction of, or loss of natural resources resulting from releases or threatened releases of hazardous substances other than during the Release;

g. liability arising from any disposal of hazardous substances at the Facility by the Settling Defendant after the lodging of this Consent Decree; and

h. criminal liability.

55. Special Reservations Regarding Natural Resource Damages.

Notwithstanding any other provision of this Consent Decree, the United States and the States reserve the right to institute proceedings against the Settling Defendant in this action or in a new action seeking recovery of Natural Resource Damages, including costs of natural resource damages assessment, based on: (i) conditions caused by the Release, unknown to the Trustees as of the date of lodging of this Consent Decree, that result in releases of hazardous substances that contribute to injury to, destruction of, or loss of Natural Resources; or (ii) information received by the Trustees after the date of lodging of this Consent Decree which indicates that the Release has resulted in injury to, destruction of, or loss of Natural Resources of a type or future persistence that was

unknown, or of a magnitude greater than was known, to the Trustees as of the date of lodging of this Consent Decree.

XV. COVENANTS BY THE SETTLING DEFENDANT

56. Covenants by the Settling Defendant. The Settling Defendant covenants not to sue and agrees not to assert any claims or causes of action against the United States or the States, or their contractors or employees, with respect to Natural Resource Damages or this Consent Decree, including but not limited to:

- a. any direct or indirect claim for reimbursement of any payment for Natural Resource Damages from the Hazardous Substance Superfund based on Sections 106(b)(2), 107, 111, 112, or 113 of CERCLA, 42 U.S.C. §§ 9606(b)(2), 9607, 9611, 9612, or 9613, or any other provision of law;
- b. any claim against the United States or the States pursuant to Sections 107 and 113 of CERCLA, 42 U.S.C. §§ 9607 and 9613, relating to Natural Resource Damages; and
- c. any claim against the United States or the States pursuant to Section 311 of the CWA, 33 U.S.C. § 1321.

57. Except as provided in Paragraph 64, the covenants in this Section shall not apply if the United States or a State brings a cause of action or issues an order pursuant to any of the reservations in Section XIV (Reservation of Rights by Plaintiffs), other than in Subparagraphs 54(a) (claims for failure to meet a requirement of the Consent Decree) or 54(h) (criminal liability), but only to the extent that the Settling Defendant's claims arise from the same response action, response costs, or damages that the United States or the State is seeking pursuant to the applicable reservation.

58. Only with respect to claims for money damages for injury or loss of property or personal injury or death arising from an exercise of rights of access under Paragraph 46, the Settling Defendant reserves, and this Consent Decree is without

prejudice to, claims against the United States, subject to the provisions of Chapter 171 of Title 28 of the United States Code, and brought pursuant to any statute other than CERCLA or RCRA and for which the waiver of sovereign immunity is found in a statute other than CERCLA or RCRA, for money damages for injury or loss of property or personal injury or death caused by the negligent or wrongful act or omission of any employee of the United States, as that term is defined in 28 U.S.C. § 2671, while acting within the scope of his or her office or employment under circumstances where the United States, if a private person, would be liable to the claimant in accordance with the law of the place where the act or omission occurred. However, the foregoing shall not include any claim based on EPA's selection of response actions, the Trustees' selection of Restoration Projects, or the oversight or approval of the Settling Defendant's deliverables or activities.

59. Nothing in this Consent Decree shall be deemed to constitute approval or preauthorization of a claim within the meaning of Section 111 of CERCLA, 42 U.S.C. § 9611, or 40 C.F.R. § 300.700(d).

60. Waiver of Certain Claims Against Other Persons. The Settling Defendant agrees not to assert any claims and to waive all claims or causes of action that it may have against all other persons for all matters relating to Natural Resource Damages, including for contribution; provided, however, that the Settling Defendant reserves the right to assert and pursue all claims, causes of action, and defenses relating to Natural Resource Damages against any person in the event such person first asserts, and for so long as such person pursues, any claim or cause of action against the Settling Defendant relating to Natural Resource Damages. Nothing in this Paragraph shall operate to waive or release any claim or action by the Settling Defendant under any contract of insurance.

XVI. EFFECT OF SETTLEMENT/CONTRIBUTION PROTECTION

61. Except as provided in Paragraph 60 (Waiver of Certain Claims Against Other Persons), nothing in this Consent Decree shall be construed to create any rights in, or grant any cause of action to, any person not a Party to this Consent Decree. Except as provided in Paragraph 60 (Waiver of Certain Claims Against Other Persons), each of the Parties expressly reserves any and all rights (including, but not limited to, any right to contribution), defenses, claims, demands, and causes of action which each Party may have with respect to any matter, transaction, or occurrence relating in any way to the Release against any person not a Party hereto.

62. The Parties agree, and by entering this Consent Decree this Court finds, that this Consent Decree constitutes a judicially approved settlement pursuant to which the Settling Defendant has resolved liability alleged in the Plaintiffs' Complaint in this action within the meaning of Section 113(f)(2) of CERCLA, 42 U.S.C. § 9613(f)(2), and is entitled to protection from contribution actions or claims as provided by Section 113(f)(2) of CERCLA, 42 U.S.C. § 9613(f)(2), for "matters addressed" in this Consent Decree. The "matters addressed" in this Consent Decree are Natural Resource Damages; provided, however, that if a Plaintiff exercises rights under the reservations set forth in Section XIV (Reservation of Rights by Plaintiffs) other than in Paragraph 54(a) (claims for failure to meet a requirement of the Consent Decree) or Paragraph 54(h) (criminal liability), the "matters addressed" in this Consent Decree will no longer include those Natural Resource Damages that are within the scope of the exercised reservation. The contribution protection afforded by this Consent Decree shall take effect upon receipt of the Settling Defendant's payment pursuant to Section VI (Payment by the Settling Defendant).

63. The Settling Defendant also agrees that, with respect to any suit or claim for contribution brought against it for matters related to this Consent Decree, the Settling

Defendant will notify the persons identified in Section XVII (Notices) in writing within 10 days of service of the complaint or claim upon it. In addition, the Settling Defendant shall notify the persons identified in Section XVII (Notices) within 10 days of service or receipt of any Motion for Summary Judgment, and within 10 days of receipt of any order from a court setting a case for trial, for matters related to this Consent Decree.

64. In any subsequent administrative or judicial proceeding initiated by the United States or a State for injunctive relief, recovery of response costs or Natural Resource Damages, or other relief relating to the Release, the Settling Defendant shall not assert, and may not maintain, any defense or claim based upon the principles of waiver, res judicata, collateral estoppel, issue preclusion, claim-splitting, or other defenses based upon any contention that the claims raised by the United States or a State in the subsequent proceeding were or should have been brought in the instant case; provided, however, that nothing in this Paragraph affects the enforceability of the Covenants Not To Sue by the Plaintiffs set forth in Section XIII.

65. This Consent Decree is not a permit, or a modification of any permit, under any federal, State, or local laws or regulations. The Settling Defendant is responsible for achieving and maintaining complete compliance with all applicable federal, State, and local laws, regulations, and permits; and the Settling Defendant's compliance with this Consent Decree shall be no defense to any action commenced pursuant to any such laws, regulations, or permits, except as set forth herein. The United States and the States do not, by their consent to the entry of this Consent Decree, warrant or aver in any manner that the Settling Defendant's compliance with any aspect of this Consent Decree will result in compliance with provisions of CERCLA, the CWA, the SWCL, or with any other provisions of federal, State, or local laws, regulations, or permits.

XVII. NOTICES

66. Whenever, under the terms of this Consent Decree, notice is required to be given or a document is required to be sent by one Party to another, it shall be directed to the individuals at the addresses or emails specified below, unless those individuals or their successors give notice of a change to the other Parties in writing. Written notice as specified herein shall constitute complete satisfaction of any written notice requirement of the Consent Decree with respect to the United States and the States, and the Settling Defendant, respectively.

67. Notices and documents submitted pursuant to this Section shall be deemed submitted upon mailing, unless otherwise provided in this Consent Decree or by mutual agreement of the Parties in writing.

68. Notice or submission to the “Plaintiffs” shall mean notice or submission to the United States (both the U.S. Department of Justice and DOI), North Carolina, and Virginia.

69. Notice or submission to the “Trustees” shall mean notice or submission to DOI, North Carolina, and Virginia.

As to the United States:

As to the U.S. Department of Justice:

EES Case Management Unit
Environment and Natural Resources Division
U.S. Department of Justice
P.O. Box 7611
Washington, D.C. 20044-7611
Re: DJ # 90-5-1-1-11057/2

or

eescdcopy.enrd@usdoj.gov

As to DOI:

Amy Horner Hanley
Senior Attorney-Advisor

Environmental Restoration Branch
Office of the Solicitor
Department of the Interior
1849 C Street, N.W.
Washington, D.C. 20240

or

amy.hanley@sol.doi.gov

As to North Carolina:

Guadalupe Carolina Fonseca Jimenez
Public Engagement Liaison
N.C. Department of Environmental Quality
1601 Mail Service Center
Raleigh, North Carolina 27699-1601

or

guadalupe.jimenez@ncdenr.gov

Drew Hargrove
Assistant General Counsel
N.C. Department of Environmental Quality
1601 Mail Service Center
Raleigh, North Carolina 27699-1601

or

drew.hargrove@ncdenr.gov

Francisco Benzoni
Special Deputy Attorney General
N.C. Department of Justice
P.O. Box 629
Raleigh, North Carolina 27602

or

fbenzoni@ncdoj.gov

As to Virginia:

Hon. Matthew J. Strickler
Secretary of Natural Resources
Commonwealth of Virginia
1111 East Broad Street
Richmond, Virginia 23219

or

natural.resources@governor.virginia.gov

Donald D. Anderson
Deputy Attorney General
Virginia Office of the Attorney General
202 North 9th Street
Richmond, Virginia 23219

Justin L. Williams
Land Protection and Revitalization Division Director/Interim Enforcement
Division Director
Virginia Department of Environmental Quality
1111 E. Main Street, Suite 1400
Richmond, Virginia 23219 or justin.williams@deq.virginia.gov

As to the Settling Defendant:

Garry S. Rice
Deputy General Counsel
Duke Energy
DEC45A 550 South Tryon Street
Charlotte, North Carolina 28202 or garry.rice@duke-energy.com

Linda D. Hickok
Manager, Environmental Services
Duke Energy
421 S. Wilmington Street, 15th Floor
Raleigh, North Carolina 27601 or linda.hickok@duke-energy.com

XVIII. APPENDICES

70. The following appendices are attached to and incorporated into this Consent Decree:

“Appendix A” is a map of the assessment area for the Release.

“Appendix B” is the draft Restoration Plan.

“Appendix C” contains the scopes of work for the Restoration Projects to be financed and completed by the Settling Defendant pursuant to Paragraph 9.

XIX. EFFECTIVE DATE AND RETENTION OF JURISDICTION

71. The Effective Date of this Consent Decree shall be the date upon which this Consent Decree is entered by the Court or a motion to enter the Consent Decree is granted, whichever occurs first, as recorded on the Court’s docket.

72. The Court shall retain jurisdiction to modify and enforce the terms and conditions of this Consent Decree and to resolve disputes arising hereunder as may be necessary or appropriate for the construction or execution of this Consent Decree.

XX. CONSENT DECREE MODIFICATIONS

73. Any material modification of this Consent Decree shall be made by agreement of the Parties to this Consent Decree and in writing, and shall not take effect unless approved by the Court. Any non-material modification of this Consent Decree shall be made by agreement of the Parties to this Consent Decree and in writing, and shall not take effect until filed with the Court. Nothing in this Consent Decree shall be deemed to alter the Court's power to enforce, supervise, or approve modifications to this Consent Decree.

74. The provisions of this Consent Decree are not severable. The Parties' consent hereto is conditioned upon the entry of the Consent Decree in its entirety without modification, addition, or deletion except as agreed to by the Parties.

75. Unanticipated or increased costs or expenses associated with the implementation of actions required by this Consent Decree and economic hardship or changed financial circumstances of the Settling Defendant shall not serve as a basis for modifications of this Consent Decree.

XXI. CONSENT DECREE TERMINATION

76. This Consent Decree may be terminated when the Plaintiffs determine that the Settling Defendant has satisfactorily completed performance of its Restoration Project obligations required by this Decree, provided that the Settling Defendant has fulfilled all other obligations of this Decree, including payment of any outstanding stipulated penalties under Section IX. The Parties shall file with the Court an appropriate joint stipulation reciting that the requirements of the Consent Decree have been met and requesting termination of the Decree.

XXII. LODGING AND OPPORTUNITY FOR PUBLIC COMMENT

77. This Consent Decree shall be lodged with the Court for a period of not less than 30 days for public notice and comment. The Plaintiffs reserve the right to withdraw or withhold their consent if comments regarding the Consent Decree disclose facts or considerations which indicate that this Consent Decree is inappropriate, improper, or inadequate. The Settling Defendant consents to the entry of this Consent Decree without further notice and agrees not to withdraw from or oppose entry of this Consent Decree by the Court or to challenge any provision of the Decree, unless the Plaintiffs have notified the Settling Defendant in writing that they no longer support entry of the Decree. If for any reason the Court should decline to approve this Consent Decree in the form presented, or if approval and entry is subsequently vacated on appeal of such approval and entry, the agreement represented by this Consent Decree is voidable at the sole discretion of any Party and the terms of the agreement may not be used as evidence in any litigation between the Parties.

XXIII. SIGNATORIES/SERVICE

78. The undersigned representatives of the Settling Defendant, the United States, and the States each certify that he or she is fully authorized to enter into the terms and conditions of this Consent Decree and to execute and legally bind such Party to this document. This Consent Decree may be executed in multiple counterparts, each of which shall be deemed an original, but all of which, taken together, shall constitute one and the same instrument.

79. The Settling Defendant shall identify, on the attached signature page, the name, address and telephone number of an agent who is authorized to accept service of process by mail or email on behalf of the Settling Defendant with respect to all matters arising under or relating to this Consent Decree. The Settling Defendant hereby agrees to accept service by either mail or email from any party to this Consent Decree and with

respect to all matters arising under or relating to this Consent Decree and to waive the formal service requirements set forth in Rules 4 and 5 of the Federal Rules of Civil Procedure and any applicable local rules of this Court including, but not limited to, service of a summons. The Settling Defendant need not file an answer to the Complaint in this action unless or until the Court expressly declines to enter this Consent Decree.

XXIV. FINAL JUDGMENT

80. This Consent Decree and its appendices constitute the final, complete, and exclusive understanding among the Parties with respect to the settlement embodied in the Consent Decree. The Parties acknowledge that there are no representations, agreements, or understandings relating to the settlement other than those expressly contained in this Consent Decree.

81. Upon approval and entry of this Consent Decree by the Court, this Consent Decree shall constitute a final judgment of the Court between and among the United States, the States, and the Settling Defendant. The Court finds that there is no just reason for delay and therefore enters this judgment as a final judgment under Fed. R. Civ. P. 54 and 58.


SO ORDERED THIS _____ DAY OF _____, _____.

United States District Judge

THE UNDERSIGNED PARTY enters into this Consent Decree in United States of America, the State of North Carolina, and the Commonwealth of Virginia, Secretary of Natural Resources v. Duke Energy Carolinas, LLC:

FOR THE UNITED STATES OF AMERICA

Date: 6/26/19



Ellen M. Mahan
Deputy Chief
Environmental Enforcement Section
Environment and Natural Resources Division
U.S. Department of Justice

Date: 6/26/19



Angela Mo
Trial Attorney
Environmental Enforcement Section
Environment and Natural Resources Division
U.S. Department of Justice
P.O. Box 7611
Washington, DC 20044-7611
(202) 514-1707
angela.mo@usdoj.gov
California Bar No. 262113

THE UNDERSIGNED PARTY enters into this Consent Decree in United States of America, the State of North Carolina, and the Commonwealth of Virginia, Secretary of Natural Resources v. Duke Energy Carolinas, LLC:

FOR THE STATE OF NORTH CAROLINA

_____

Date:


_____

Sheila Holman
Assistant Secretary for the Environment
N.C. Department of Environmental Quality
1601 Mail Service Center
Raleigh, North Carolina 27699-1601
(919) 707-8619
sheila.holman@ncdenr.gov

THE UNDERSIGNED PARTY enters into this Consent Decree in United States of America, the State of North Carolina, and the Commonwealth of Virginia, Secretary of Natural Resources v. Duke Energy Carolinas, LLC:

FOR THE COMMONWEALTH OF
VIRGINIA


Date:


7-18-19

Mark R. Herring, Attorney General
Donald D. Anderson, Deputy Attorney General
Paul Kugelman, Jr., Senior Assistant Attorney
General/Chief

Daniel W. Ingersoll, Assistant Attorney General
202 North 9th Street
Richmond, Virginia 23219
(804) 786-3806
dingersoll@oag.state.va.us

Date:


7/15/19

Matthew J. Strickler
Secretary of Natural Resources
Commonwealth of Virginia

THE UNDERSIGNED PARTY enters into this Consent Decree in United States of America, the State of North Carolina, and the Commonwealth of Virginia, Secretary of Natural Resources v. Duke Energy Carolinas, LLC:

FOR DUKE ENERGY CAROLINAS, LLC



Date:

5/8/19


Paul Draovitch
Senior Vice President
Environmental Health & Safety
Duke Energy Carolinas, LLC
526 Church Street
Mail Code EC3XP
Charlotte, North Carolina 28202
(980) 373-0408
Paul.Draovitch@duke-energy.com

Agent Authorized to Accept Service on Behalf of Above-Signed Party:

CT Corporation System
160 Mine Lake Court, Suite 200
Raleigh, North Carolina 27615

Consent Decree

Appendix A



Map of assessment area for Dan River Coal Ash Release February 2, 2014.

Consent Decree

Appendix B

**DRAFT RESTORATION PLAN and ENVIRONMENTAL
ASSESSMENT**

FOR THE

**DAN RIVER COAL ASH SPILL
NATURAL RESOURCE DAMAGE ASSESSMENT AND
RESTORATION**

April 2019 DRAFT

Prepared by

Dan River Natural Resource Trustee Council:

United States Fish and Wildlife Service
North Carolina Department of Environmental Quality
Virginia Department of Environmental Quality



Table of Contents

1.0	INTRODUCTION	4
1.1	Purpose and Need for Restoration	4
1.2	Natural Resource Trustees and Authority	5
1.3	Public Participation	6
1.4	Overview of the Dan River Coal Ash Spill.....	7
1.5	Summary of the Proposed Settlement Agreement	9
1.6	Organization of the Dan River Restoration Plan and Environmental Assessment	9
2.0	SUMMARY OF INJURY TO NATURAL RESOURCES, RESTORATION SCALING AND DAMAGES DETERMINATION.....	10
3.0	RESTORATION ALTERNATIVES.....	13
3.1	Restoration Scoping	13
3.2	Restoration Alternatives Evaluation Criteria	14
3.3	Potential restoration alternatives identified during Restoration Scoping.....	14
3.4	Proposed Restoration Alternatives (and other alternatives considered but eliminated)	15
	Alternative 1: No Action.....	17
	Alternative 2: Mayo River Conservation (preferred)	17
	Alternative 3 - Abreu Grogan Park Improvements (preferred)	19
	Alternative 4 - Pigg River Power Dam Removal (preferred)	19
	Alternative 5: Establishment of Public Boat Launch Facilities on the Dan River (preferred)	20
	Alternative 6A: Rare and Nongame Species Restoration (Mussels)	20
	Alternative 6B: Rare and Nongame Species Restoration (Roanoke logperch)	21
	Alternative 7: Water Quality Improvements via Supplemental Support for Virginia Agricultural Cost Share Program	22
4.0	ENVIRONMENTAL ASSESSMENT	22
4.2	Environmental Consequences of the No Action Alternative and Preferred Alternatives	27
4.2.1	Environmental Consequences of the No Action Alternative	28
4.2.2	Environmental Consequences of the Preferred Alternatives	29
4.3	Summary of Cumulative Impacts	29
5.0	PROJECT FULFILMENT AND MONITORING	34
6.0	REFERENCES	36

List of Tables

Table 1:	Summary of Natural Resource and Service Benefits of Proposed Restoration Alternatives
Table 2:	Summary of Environmental Consequences of the No Action and Preferred Alternatives

List of Figures

Figure 1:	Watershed Map for the Dan River Coal Ash Spill
Figure 2:	Locations of Preferred Restoration Alternatives

List of Appendices

Appendix A:	Abreu Grogan Park Amenity Summary
Appendix B:	Pigg River Dam Restoration at Power Dam; Year 1 Monitoring Report
Appendix C:	List of Species classified as rare, threatened, endangered or of special concern in the Dan and Mayo River Basins

List of Acronyms and Abbreviations

CEQ	Council on Environmental Quality
CERCLA	Comprehensive Environmental Response, Compensation, and Liability Act
COPC	Contaminants of Potential Concern
CWA	Clean Water Act (or Federal Water Pollution Control Act)
DOI	United States Department of the Interior
DRNRTC	Dan River Natural Resource Trustees Council
FORVA	Friends of the Rivers of Virginia
HEA	Habitat Equivalency Analysis
NCP	National Oil and Hazardous Substances Pollution Contingency Plan
NCDEQ	North Carolina Department of Environmental Quality
NCDWQ	North Carolina Division of Water Quality
NCWRC	North Carolina Wildlife Resources Commission
NEPA	National Environmental Policy Act
NRD	Natural Resource Damages
NRDAR	Natural Resource Damage Assessment and Restoration
PAS	Preliminary Assessment Screen and Determination
RP/EA	Restoration Plan and Environmental Assessment
SESD	Science and Ecosystem Support Division
TMDL	Total Maximum Daily Load
USEPA	United States Environmental Protection Agency
USFWS	United States Fish and Wildlife Service
VADCR	Virginia Department of Conservation and Recreation
VADEQ	Virginia Department of Environmental Quality

1.0 INTRODUCTION

The United States Department of the Interior (DOI) acting through the U.S. Fish and Wildlife Service (USFWS), the Commonwealth of Virginia acting through the Virginia Department of Environmental Quality (VADEQ), and the State of North Carolina acting through the North Carolina Department of Environmental Quality (NCDEQ), collectively the Dan River Natural Resource Trustee Council (Trustees, or DRNRTC) initiated a natural resource damage assessment and restoration (NRDAR) process to determine and quantify injuries to natural resources and resource services resulting from the release of hazardous substances at and from the Duke Energy Dan River Steam Station in Rockingham County, NC to the waters of, and to the habitats associated with, the Dan River (Figure 1). As part of the NRDAR process, the Trustees must also identify and select restoration actions that will compensate for the injured resources and services and seek to recover compensation from the entity responsible for the injuries to natural resources and lost services.




Figure 1. Watershed Map for the Dan River Coal Ash Spill

1.1 Purpose and Need for Restoration

This Draft Restoration Plan/Environmental Assessment (RP/EA) has been prepared by the Trustees to address natural resources injured and ecological services lost due to releases of hazardous substances associated with coal ash from the Dan River Steam Station in February 2014 (Spill). The purpose of this Draft RP/EA is to present the “preferred alternative” restoration project or projects that will accomplish the goal of restoring, rehabilitating, replacing and/or acquiring the equivalent of those natural resources, and the services those resources provide, that have been injured from the release. The Trustees developed this Draft RP/EA in accordance with 43 C.F.R. § 11.93 to inform the public as to the types and scale of

restoration to be undertaken towards compensating for injuries to natural resources. Consistent with the CERCLA NRDAR regulations, this Draft RP/EA includes a reasonable number of restoration alternatives and identifies a preferred alternative. Public comments are being sought on this Draft RP/EA and will be considered and incorporated in the final RP/EA as appropriate.

1.2 Natural Resource Trustees and Authority

Pursuant to the authority of Section 107(f) of the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA), as amended, 42 U.S.C. § 9607(f); Federal Water Pollution Control Act (commonly known as the Clean Water Act), as amended, 33 U.S.C. § 1321(f)(4) and (5), (CWA); Subpart G of the National Oil and Hazardous Substances Pollution Contingency Plan (NCP), 40 C.F.R. §§ 300.600, 300.605; and other applicable Federal and State laws, designated Federal and State authorities may act on behalf of the public as natural resource trustees to pursue natural resource damages for injury to, destruction of, or loss of natural resources and their services resulting from the release of hazardous substances to the environment.

The President has designated Federal resource trustees in the NCP, 40 C.F.R. § 300.600, and through Executive Order 12580, dated January 23, 1987, as amended by Executive Order 13016, dated August 28, 1996. Pursuant to the NCP, the Secretary of the DOI acts as a Trustee for natural resources and their supporting ecosystems, managed or controlled by the DOI. In this matter, the USFWS is acting on behalf of the Secretary of the DOI as Trustee for natural resources under its jurisdiction, including but not limited to migratory birds and endangered and threatened species.

In accordance with 42 U.S.C. § 9607(f)(2)(B) and the NCP, the Virginia Secretary of Natural Resources has been designated the natural resource Trustee by the Governor of Virginia. The State of North Carolina has designated the Secretary of the NCDEQ as its Natural Resource Trustee representative. The State Trustees act on behalf of the public as Trustee for natural resources, including their supporting ecosystems, within the boundaries of their state, or belonging to, managed by, controlled by, or appertaining to Virginia and North Carolina, respectively.

The State and Federal Trustees may have overlapping jurisdiction over the natural resources potentially affected in this matter. This shared trusteeship is reflected in the coordinated wildlife management practices of the USFWS, North Carolina, and Virginia, and is consistent with the management policies of North Carolina, Virginia, and the USFWS.

This Draft RP/EA was prepared jointly by the Trustees in accordance with Section 111(i) of CERCLA and its implementing regulations (43 C.F.R. § 11.93). In addition, federal trustees must comply with the National Environmental Policy Act (NEPA), 42 U.S.C. § 4321 et seq., and its regulations, 40 C.F.R. § 1500 et seq., when planning restoration projects. NEPA requires a federal agency to consider the potential environmental impacts of a planned federal action(s)

to determine if the proposed action(s) may significantly affect the environment and to inform and involve the public in the decision-making process. In compliance with NEPA, this Draft RP/EA summarizes the current environmental setting where the proposed restoration actions may take place, describes the purpose and need for restoration actions, and identifies alternatives and their potential environmental consequences and provides an environmental analysis of the restoration actions. As described in Sections 3.0 and 4.0, Duke Energy completed several of the preferred restoration alternatives voluntarily, without federal funds. These completed projects include the Abreu Grogan Park Improvements, Pigg River Power Dam Removal, and conservation of Mayo River through acquisition of property and conveyance to the Commonwealth of Virginia and the State of North Carolina. Prior to completing this subset of preferred restoration alternatives, Duke Energy complied with applicable environmental laws, and obtained permits and other approvals, where necessary. Consistent with federal laws, the DOI is continuing to evaluate the preferred restoration alternatives identified in this Draft RP/EA that are not yet complete for compliance with other applicable laws. Once finalized, these additional environmental compliance evaluations will be included as appendices to the Final Restoration Plan and Environmental Assessment for the Dan River Coal Ash Spill. For the Draft RP/EA, other potentially applicable laws and regulations include:

- *The Endangered Species Act (ESA), (16 U.S.C. § 1531, et seq.)*
- *Clean Water Act, (33 U.S.C. § 1251, et seq.)*
- *National Historic Preservation Act of 1966, (16 U.S.C. § 470 et seq.)*

1.3 Public Participation

Public participation is an important step in the NRDAR and NEPA processes. The Trustees have worked to engage local communities and other stakeholders in the NRDAR process since the Spill, beginning with meetings in the early stages of the Spill to introduce the NRDAR process to interested members of the public. The public was also invited to propose projects for review and incorporation into this Draft RP/EA. Public review of the Draft RP/EA Plan is an integral component of both NEPA and the CERCLA NRDAR process pursuant to 43 C.F.R. § 11.81(d)(2) and § 11.93. Through the public review process, the Trustees seek public comment on the restoration alternatives and the Trustees' preferred restoration alternatives to restore injured natural resources or replace resource services lost as a result of the Spill.

The Draft RP/EA will be open for public comment for 45 days from the date of publication of the Notice of Availability in the Federal Register. Interested individuals, organizations, and agencies may submit comments by writing or emailing either:

Sara Ward, U.S. Fish and Wildlife Service
Raleigh Ecological Services Field Office
Phone: 252-473-1132 Ext. 243
Email: Sara_Ward@fws.gov,

or

Susan Lingenfelser, U.S. Fish and Wildlife Service
Virginia Ecological Services Field Office
Phone: 804-824-2415
Email: Susan_Lingenfelser@fws.gov

The Trustees will review and consider all public comments and input on the Draft RP/EA received during the public comment period prior to finalizing the RP/EA. The Trustees will prepare a responsiveness summary to the comments that will be included as an appendix in the Final Dan River Restoration Plan and Environmental Assessment. The development of the Draft RP/EA, the public comment process, and finalization of the Restoration Plan and Environmental Assessment is performed solely by the Trustees. Based on the public's comments, or other information, the Trustees may amend the RP/EA if significant changes are made to the type, scope, or impact of the projects. In the event of a significant modification to the RP/EA the Trustees will provide the public with an opportunity to comment on that particular amendment.

The notice of availability of the Draft RP/EA and opportunity for the public to provide comments will be referenced in a Federal Register Notice of Availability and notice of availability will be published in Eden Daily News, Greensboro News and Record, and Danville Register & Bee.

Trustees have maintained records documenting the information considered and actions taken during this NRDAR process. These records are available on the [Dan River Coal Ash NRDAR website](#). Physical copies of the records are also available for review by interested members of the public at the USFWS Virginia Field Office, 6669 Short Lane, Gloucester, VA 23061. However arrangements must be made in advance to review or obtain copies of these records by contacting:

Susan Lingenfelser, U.S. Fish and Wildlife Service
Virginia Ecological Services Field Office
Phone: 804-824-2415
Email: Susan_Lingenfelser@fws.gov

Access to and copying of these records is subject to all applicable laws and policies, including, laws and policies relating to copying fees and the reproduction or use of any material that is copyrighted.

1.4 Overview of the Dan River Coal Ash Spill

The Dan River Coal Ash Spill began on or around February 2, 2014, from the collapse of a stormwater pipe beneath a coal ash slurry impoundment at the Duke Energy Dan River Steam Station (Site).

Ash material and ash pond water within the reservoir were released into the Dan River as a result of failure of a 48-inch diameter stormwater pipe comprised of concrete and corrugated metal. Up to an estimated 39,000 tons of ash and 27 million gallons of ash pond water were released into the Dan River. Coal ash is a gray, powdery byproduct of burning coal to produce energy. Coal ash is composed of materials remaining after coal is burned, including fine sand (called silica), unburned carbon, and various trace metals such as arsenic, boron, cadmium, chromium, copper, lead, mercury, nickel, selenium, and zinc; compounds that have potential to be chemicals of concern associated with the Dan River Coal Ash Spill. The Facility is less than 10 river miles from Virginia, and USFWS reconnaissance documented ash or ash-like material comingled with native sediment as far as 70 river miles downstream in the days immediately following the Spill.

Three removal actions were conducted related to the Spill. On February 8, 2014, a coal ash bar about 75 feet long and 15 feet wide which had as much as five feet of ash or ash/sand mix over the natural stream bottom was identified and subsequently removed (February 11-13, 2014), resulting in the recovery of 15 tons of coal ash and native sediment. Completion of the removal of a coal ash deposit (258 tons of a coal ash and river sediment mixture) occurred on July 7, 2014 at a location approximately two miles downstream from the Site on a native sandbar delta at the mouth of Town Creek with the Dan River. Removal of 2,500 tons of coal ash comingled with native sediment in a larger deposit upstream of the Schoolfield Dam in Danville, VA began on May 6, 2014, and was also completed in early July 2014 (although Abreu Grogan Park, where cleanup equipment was mobilized, was closed to public use to support cleanup activities between April 1 - August 1, 2014). In addition to these removal actions, a total of about 466 cubic yards of solids (ash/sediment mix) were removed from the water treatment plants at Danville and South Boston, VA and properly disposed of along with dredged material from the Dan River.

Pursuant to the CERCLA NRDAR regulations (43 C.F.R. §§ 11.23-11.25), the Trustees completed a Preliminary Assessment Screen and Determination (PAS) for the Dan River Coal Ash Spill in March, 2014. Based on the information in the PAS, the Trustees determined to proceed with the NRDAR process, provided a Notice of Intent to Conduct a Natural Resource Damage Assessment to the potentially responsible party, Duke Energy, and invited Duke Energy to participate in a cooperative NRDAR process. Duke Energy and the Trustees agreed to enter into a cooperative assessment agreement in order to facilitate the resolution of any claims for natural resource damages (NRD)¹. See [*Funding and Participation Agreement Between \[sic\] the State of North Carolina, the Commonwealth of Virginia, the U.S. Department of the Interior, and Duke Energy Carolinas, LLC, Concerning Cooperative Natural Resource Damage Assessment, Restoration Planning, and Restoration Implementation Activities for the Duke Energy Dan River Steam Station Coal Ash Pond Site in Rockingham, NC. June 2014.*](#)

¹ Although the NRDAR was cooperative with Duke Energy, this Draft RP/EA is solely the work of the Trustees and is not in any way attributable to Duke Energy.

Also in accordance with CERCLA NRDAR regulations (43 C.F.R. § 11.32), in June, 2015 the Trustees released a draft Assessment Plan for the Dan River Coal Ash Spill for public review and comment. A [final Assessment Plan](#) was completed in December 2015. As described in the Assessment Plan, the Trustees defined the Area of Assessment to include the point of discharge from the Facility's storm sewer management pipe in Rockingham County, North Carolina downstream (approximately 77 river miles) to and including Buggs Island Lake (John H. Kerr Reservoir), located in Virginia and North Carolina. In conducting the NRDAR, whenever possible, the Trustees coordinated damage assessment activities with other investigations to satisfy the Trustees' NRDAR objectives in a cost and resource efficient manner. The natural resources and services that were identified in the Assessment Plan to be of interest to the Trustees during the assessment are described further below (see "Summary of Injury to Natural Resources, Restoration Scaling, and Damages Determination").

1.5 Summary of the Proposed Settlement Agreement

A proposed settlement agreement among the Trustees and Duke Energy was documented in a consent decree which was lodged with the federal court and open for a forty-five (45) day public comment period concurrent with this Draft RP/EA. A Notice of Availability for the Consent Decree and draft RP/EA was published in the Federal Register. Under the terms of the proposed settlement, the Trustees will provide covenants not to sue to Duke Energy for NRD under CERCLA, the CWA, and applicable state laws. Duke Energy has performed several projects, and agrees to perform several additional restoration projects to compensate for the injured, lost, or destroyed resources and services resulting from the Dan River Coal Ash Spill. In addition, as part of the cooperative assessment process for the Dan River Coal Ash Spill NRDAR, Duke Energy has previously reimbursed the Trustees for assessment costs incurred. During the public comment period, the proposed consent decree will be available for public review and comment at <https://www.justice.gov/enrd/consent-decrees>.

1.6 Organization of the Dan River Restoration Plan and Environmental Assessment

Chapter 2 provides a brief summary of the Trustees' assessment of injury to natural resources and their services as a result of exposure to hazardous substances from the Dan River Coal Ash Spill. The Trustees assessed exposure of natural resources to coal-ash related hazardous substances and determined injuries to a variety of natural resources, including surface water, sediment, and various biota, as a result of that exposure. As part of the NRDAR, the Trustees evaluated the amount of restoration necessary to compensate the public for injuries to these resources for the period between the onset of injury and the resource's return to baseline (DRNRT 2015).

Chapter 3 describes the proposed restoration alternatives the Trustees identified and evaluated to return the resources injured by the Dan River Coal Ash Spill to their pre-release condition and to compensate for the interim loss pending restoration. This includes a summary of the restoration scoping activities the Trustees conducted in 2014 and 2015

and the criteria with which the Trustees evaluate possible restoration alternatives. 43 C.F.R. § 11.82(d) and § 11.93.

Chapter 4 describes the affected environment where the preferred restoration alternatives would be implemented and presents the Trustees' analysis of the environmental consequences of the preferred restoration alternatives.

Chapter 5 provides the monitoring and project fulfillment, Chapter 6 provides the Trustees' conclusions, and Chapter 7 contains the references identified in this Draft RP/EA.

2.0 SUMMARY OF INJURY TO NATURAL RESOURCES, RESTORATION SCALING AND DAMAGES DETERMINATION

Coal ash is produced through the burning of coal in coal-fired power plants, among other activities. Coal ash includes a number of by-products, such as fly ash, a fine, powdery material, or bottom ash, a coarse and angular ash particle. (See <https://www.epa.gov/coalash/coal-ash-basics> for more information). Coal ash is composed of materials remaining after coal is burned, including fine sand (called silica), unburned carbon, and various metals such as arsenic, boron, cadmium, chromium, copper, lead, mercury, nickel, selenium, and zinc. Various samples were collected from the ash pond, ash/native sediment deposit adjacent to the Site, and surface waters in the Dan River and analyzed for ash-related contaminants of potential concern (COPC). The data from these samples indicate that COPC levels (including, but not limited to, arsenic, copper, selenium, iron, turbidity, zinc, and lead) exceeded action and guidance levels for ecological receptors following the Spill (DRNRTC 2014a). Coal ash releases into the environment can create a suite of impacts to natural resources and the services they provide. In aquatic environments, coal ash can impact aquatic organisms through chemical (direct contact with suspended or dissolved hazardous substances in the water column, direct contact with sediments contaminated by hazardous substances associated with coal ash, direct contact with contaminated sediment interstitial pore water, exposure by re-suspended, pre-contaminated sediments, ingestion of contaminated sediment during foraging or feeding, and/or indirect contact through ingestion of contaminated prey species, including bioaccumulation) exposure. Natural resources and associated services under the jurisdiction of the Trustees that may have been injured by the Spill include:

- stream and wetland habitat
- surface water and sediment
- aquatic biota
- migratory birds
- human recreational uses

The Trustees conducted NRDAR activities, including: reviewing data from the Spill response efforts to assess injuries to natural resources at and downstream of the Site, to where the coal ash came to be located; preparing a natural resource damage assessment plan; soliciting input

from the public and interested stakeholders on the scoping document for restoration planning; and considering restoration project proposals submitted by the public (See Chapter 3.0, Proposed Restoration Alternatives, for additional information). Based on information developed and analyzed by the Trustees, the Trustees determined that the concentrations of hazardous substances in surface water and sediment of Dan River were at levels sufficient to cause injury² to fish and other aquatic biota, as evidenced by exceedances of freshwater aquatic life criteria and consensus-based probable effects concentrations for freshwater ecosystems (DRNRT 2014a).

In the damages determination phase of the NRDAR process, the Trustees identified and used procedures to determine the type and magnitude of restoration needed to bring injured natural resources to the appropriate baseline condition and to address the public's loss of natural resource services for the period from the time of release to restoration to baseline (the "interim loss") (DRNRT 2015). The scale (or size) of the restoration action(s) should be that which provides the value to adequately offset the natural resource and service losses. The process of determining the size of restoration is called restoration scaling. Restoration scaling requires a framework for quantifying the losses and for quantifying the benefits of restoration so the losses and benefits can be compared. For restoration scaling, the Trustees evaluated two decision support models: an ecological service model and a human-use services model. The ecological service model evaluates the ecological service losses associated with the Spill and the ecological service benefits of proposed restoration projects to offset the ecological service losses. The human-use services model evaluates the fishing and outdoor recreation losses associated with the Spill and the benefits of restoration projects that offset the human-use losses.

The ecological service model incorporated a Habitat Equivalency Analysis (HEA) that evaluated the interim losses and the expected service benefits of proposed restoration projects. HEA is a service-to-service or resource-to-resource approach to natural resource valuation that can account for changes in baseline³ services while estimating interim losses of services. Baseline service losses include the loss of resources as compared to their baseline condition (i.e., the condition they would be in now had no contamination occurred). Interim losses include the losses over the time when resources are in an impaired condition and less available to the public. Primary restoration projects (including property acquisition) are used to bring resources to baseline condition, while compensatory restoration projects are used to offset the interim

² "Injury" as defined in CERCLA NRDAR regulations means "a measurable adverse change, either long- or short-term, in the chemical or physical quality or the viability of a natural resource resulting either directly or indirectly from exposure to a discharge of oil or release of a hazardous substance, or exposure to a product of reactions resulting from the discharge of oil or release of a hazardous substance. As used in this part, injury encompasses the phrases 'injury,' 'destruction,' and 'loss.'" 43 C.F.R. § 11.14 (v).

³ "Baseline" is defined in CERCLA NRDAR regulations as "the condition or conditions that would have existed at the assessment area had the discharge of oil or release of the hazardous substance under investigation not occurred." 43 C.F.R. § 11.14 (e).

loss. The fundamental concept in HEA is that compensation for lost ecological services can be provided by restoration projects that provide comparable services.

The Trustees estimated lost services of natural resources (e.g., benthic invertebrates, fish, mussels) resulting from the Dan River Coal Ash Spill including:

- exposure to suspended or dissolved hazardous substances through ash covering⁴
- ash removal⁵
- exceedance of selected U.S. Environmental Protection Agency (USEPA) screening criteria for arsenic and selenium in surface water⁶
- exceedance of selected USEPA screening criteria for arsenic and selenium in sediment⁷

The HEA accounted for the geographic scope of the affected area, estimates of ash deposits throughout the affected area, baseline conditions in the Dan River, service losses related to the three impacts identified above, and the timing of these impacts. The percent of coal ash that is deposited temporally and spatially throughout the affected area provides a pathway to suspended or dissolved hazardous substances exposure and was determined using data from the Sediment Transport Model (Altinakar et al. 2015) developed for the Spill. Other sources of data (DRNRTC 2015, HDR 2015) used to evaluate potential impacts include:

- surface water quality samples collected by Duke Energy, USEPA, NCDEQ, and VADEQ
- sediment quality samples
- pre-and post-spill benthic and fish community structure data including a post spill mussel survey (Alderman and Alderman 2014)
- fish-tissue metals concentrations

In addition to injuries to the natural resources, the release of hazardous substances at and from the Site negatively affected recreational uses and opportunities in the Dan River watershed such as sport fishing, water-contact recreation, boating, canoeing, hiking, nature observation, hunting, and other activities. Public use and access was restricted at the Abreu Grogan Park in

⁴ A Sediment Transport Model was used to develop an estimate of the relative ash covering, the exposure pathway to suspended or dissolved hazardous substances, in defined river reaches (Altinakar et al. 2015). Field based confirmation of ash deposition was also performed.

⁵ According to the May 2014 Administrative Settlement Agreement and Order on Consent for Removal Action, Duke Energy dredged a total of 3,062 cubic yards (or a total of 1.90 acre-feet of ash removal) in three different locations upstream of Schoolfield Dam (USEPA 2014).

⁶ Surface water grab samples were collected by Duke Energy, USEPA (Superfund Technical Assessment and Response Team and Science and Ecosystem Support Division [SESD]), NCDENR, and VADEQ. At a subset of sediment sampling locations (with sufficient water depth), USEPA Region 4's SEDS team collected water column samples (including a minimum of a surface and sediment/water interface grab sample). Results were compared to federal ambient water quality standards to determine areas affected by exceedances.

⁷ Sediment samples were also collected from the river by USEPA at intervals along the Dan River in areas immediately downstream (including through Danville, VA) and then at greater spatial intervals throughout the remaining riverine portion of the Dan River system. Results were compared to USEPA screening levels for selenium and arsenic to determine areas affected by exceedances.

Danville, NC, which provides the only public boat access point on the Dan River between the Dan River Steam Station dam in Eden, NC and the Schoolfield Dam in Danville, VA. The Abreu Grogan Park was closed to public use while cleanup equipment was mobilized and during the removal of a coal ash deposit in the river in the vicinity of the Schoolfield Dam between May 6 and August 1, 2014). Closures, regulatory advisories, and other warnings occurring as a result of the release from the Site included: a recreational water advisory in North Carolina (between February 12 and July 22, 2014) and a fish consumption advisory in the counties of Rockingham and Caswell, NC (between February 12, 2014 and November 29, 2017, NCDHHS 2017).

An assessment of lost recreational uses as a result of the Spill and the benefits from proposed restoration projects for recreational uses was evaluated via benefit transfer. Benefit-transfer uses existing recreational use preference information from the economics literature to identify how changes in environmental quality or site characteristics could affect a recreational user's well-being (e.g., anglers). The benefit-transfer model combines this preference information with data on the potentially affected population, information on potential substitute sites, and information on the number of trips taken to the affected area and set of potential substitute sites. In general, the benefit-transfer model attempts to evaluate recreational use behavior (fishing and general outdoor use) under With- and Without-Release conditions to estimate the losses from the coal ash Spill, and With- and Without-Restoration to estimate the benefits of restoration.

3.0 RESTORATION ALTERNATIVES

Restoration of resources injured and services lost by the Spill is the goal of the Dan River Coal Ash NRDAR process. The purpose of the actions identified in this RP/EA is to restore, rehabilitate, replace, or acquire the equivalent of natural resources that were injured or destroyed and recreational use that was lost because of the Spill pursuant to the requirements of applicable federal and state laws and regulations.

3.1 Restoration Scoping

In October 2014, the Trustees released a Scoping Document for Restoration Planning (Scoping Document) (DRNRTC 2014b). The Scoping Document provided information on the Spill, the potential natural resource injuries resulting from the Spill, restoration project concepts for the resources affected by the Spill, and an explanation of the restoration planning process, including restoration project eligibility and evaluation criteria. Review of the projects described in the Scoping Document promoted public engagement early in restoration planning and provided the public an opportunity to show support for the types of projects under consideration to restore natural resources and their services or provide other restoration project ideas to the Trustees. Feedback from the public showed great support for public river access, land protection and conservation projects such as the Mayo Tract as well as dam removal and other projects that protect water quality in the river. A Restoration Scoping Response Summary of the feedback received by the Trustees on the Scoping Document for Restoration Planning was finalized in December 2014 (DRNRTC 2014c). The restoration scoping

process led to a final document that provided a comprehensive list of potential restoration projects and existing restoration opportunities in the Dan River watershed area, partnerships with stakeholders (e.g., conservation organizations and river users), more public engagement, and identification of potential concerns with possible restoration actions (DRNRTC 2014b). For purposes of this draft Restoration Plan, the Trustees are using the same *criteria* for evaluation of restoration alternatives as were used in the Scoping Document, as described in the next section. The Scoping Document also identified *potential restoration alternatives* to guide the restoration planning process, which are summarized in Section 3.4.

3.2 Restoration Alternatives Evaluation Criteria

Eligibility criteria for evaluation of restoration alternatives are outlined in the CERCLA NRDA regulations (43 C.F.R. § 11.82(d)). The Trustees used additional case-specific alternative selection criteria to assess the potential restoration alternatives as follows:

- Nexus – the alternative has a connection to the restoration, rehabilitation, replacement, and/or acquisition of the equivalent of the injured natural resources or lost services.
- Relevance – the alternative effectively meets restoration goals and objectives.
- Cost Reasonableness – the cost of the proposed restoration alternative is reasonable in relationship to the injury, and benefits to the injured resources can be quantified; opportunities to share costs with other organizations and/or agencies may be available and are considered.
- Measurable – an alternative delivers tangible and specific resource restoration results that are identifiable and measurable.
- Efficacy – it is likely that a restoration alternative will be successful based on consideration of future operation and maintenance requirements and vulnerability of the alternative to natural or human-induced stresses following implementation.
- Legality – the restoration alternative complies with applicable/relevant Federal, State, and local laws and regulations.
- Ecological leverage – the restoration alternative promotes other environmental benefits, avoids collateral injury to natural resources as a result of implementation, and is not subject to an independent, prior obligation.
- Compatibility – the alternative is compatible with the surrounding land use.

3.3 Potential restoration alternatives identified during Restoration Scoping

Through consideration of the criteria described above and the natural resources and associated services affected by the Spill (habitat, surface water and sediment, aquatic biota, migratory birds, and human uses), the Trustees identified the following categories of restoration alternatives appropriate for consideration to offset injuries related to the Spill:

- Avoided Habitat Loss via Land Acquisition/Protection
- Restoration of In-stream Habitat/Fish Passage

- Restoration of Riparian and Wetland Habitat
- Rare and Nongame Species Restoration
- Improve quality of fishing experience
- Expand river-centered opportunities for public recreation and wildlife viewing

The Trustees identified proposed alternatives for restoration of natural resources and recreational opportunities based on an evaluation of the criteria and types of restoration alternatives described above. A description of the proposed restoration alternatives and their environmental benefits are described in Section 3.4.

3.4 Proposed Restoration Alternatives (and other alternatives considered but eliminated)


Each restoration alternative identified by the Trustees is described in more detail in this section. As a result of the public feedback generated by the Trustees' restoration scoping activities, Duke Energy has pursued implementation of several of the restoration alternatives. Consequently, in this document, the Trustees are evaluating the suitability of alternatives (some of which have already been implemented by Duke Energy and others which have yet to be implemented) to offset injuries to natural resources and services resulting from the Spill. Table 1 indicates the category or categories of restoration satisfied by each proposed alternative to compensate for natural resource injury and lost recreational use in the Dan River and highlights the completion status of the various alternatives. Table 1 also identifies the Trustees' preferred alternative restoration projects that will accomplish the goal of restoring, rehabilitating, replacing and/or acquiring the equivalent of those natural resources, and the services those resources provide. Figure 2 illustrates the locations of each of the preferred alternatives completed and area of focus for those in progress.

Table 1. Summary of Natural Resource and Service Benefits of Restoration Alternatives

Restoration Alternative	Restoration Categories	Natural Resources and Services Benefited	Status
1 - No Action	<ul style="list-style-type: none"> • None 	None	Considered, but eliminated from further analysis
2 - Mayo River Conservation (preferred)	<ul style="list-style-type: none"> • Avoided habitat loss via land protection • Expand river centered opportunities for public recreation/wildlife viewing • Improve quality of the fishing experience 	<ul style="list-style-type: none"> • habitat • surface water and sediment • aquatic biota • migratory birds • human uses 	618.72 acres conserved and transferred to North Carolina and Virginia State Parks; up to 64.403 additional acres remaining to be acquired (in progress)
3 - Abreu Grogan Park Improvements (preferred)	<ul style="list-style-type: none"> • Improve quality of fishing experience 	<ul style="list-style-type: none"> • human uses 	Completed

4 - Pigg River Power Dam Removal (preferred)	<ul style="list-style-type: none"> Expand river-centered opportunities for public recreation and wildlife viewing 		
	<ul style="list-style-type: none"> Restoration of In-stream Habitat/Fish Passage Restoration of Riparian and Wetland Habitat Rare and Nongame Species Restoration Expand river centered opportunities for public recreation/wildlife viewing/fishing experience 	<ul style="list-style-type: none"> habitat surface water and sediment aquatic biota migratory birds human uses 	Dam demolition completed; environmental monitoring ongoing
5 - New Public Boat Launch Facilities on the Dan River (preferred)	<ul style="list-style-type: none"> Improve quality of fishing experience Expand river-centered opportunities for public recreation and wildlife viewing 	<ul style="list-style-type: none"> human uses 	Planning in progress
6A – Rare and Nongame Species Restoration (Mussels)	<ul style="list-style-type: none"> Rare and Nongame Species Restoration 	<ul style="list-style-type: none"> aquatic biota 	Community mussel restoration strategy considered but eliminated from further analysis
6B – Rare and Nongame Species Restoration (Roanoke logperch)	<ul style="list-style-type: none"> Rare and Nongame Species Restoration 	<ul style="list-style-type: none"> aquatic biota 	Considered, but eliminated from further analysis
7 – Water Quality Improvements (SL-6 Projects)	<ul style="list-style-type: none"> Restoration of In-stream Habitat/Fish Passage Restoration of Riparian and Wetland Habitat 	<ul style="list-style-type: none"> aquatic biota 	Considered, but eliminated from further analysis

Figure 2. Locations of Preferred Restoration Alternatives



Alternative 1: No Action

Under this alternative, no restoration activities beyond what have been presented in the [EPA-approved response and cleanup activities](#) will be conducted at the Site (USEPA 2014). The underlying assumption of this alternative is that natural resources and the services they provide will recover over time through natural attenuation. This alternative is appropriate if/when no additional restoration projects are necessary to restore, rehabilitate, replace, and/or acquire the equivalent of the injured natural resources. This alternative has no cost.

The no action alternative is not appropriate for the Dan River Spill given that interim losses to natural resources and the services they provide (as evidenced by recreational and fish consumption resources and park closures) cannot be addressed through natural attenuation.

Alternative 2: Mayo River Conservation (preferred)

This restoration alternative involves the acquisition and conservation of up to 618.72 acres of floodplain and riverbank properties along the Mayo River and ultimate transfer to the Mayo River State Parks in North Carolina and Virginia for long term stewardship and conservation in

perpetuity as part of the North Carolina and Virginia Mayo River State Parks, respectively. Mayo River corridor parcels in North Carolina were frequently mentioned in responses to the Trustees' restoration scoping request in 2014. The acquisition and conservation of this corridor as part of the Mayo River State Park protects a significant aquatic habitat with high quality water and with at least 10 rare and listed aquatic species and adjacent terrestrial natural heritage features. This addition to the state parks would allow greater access and safety for the public to over 10 miles of the Mayo river for increased river-based recreation and fishing, as well as typical state park camping, hiking, and environmental education. In Virginia, the Virginia General Assembly in 2007 authorized a study of the feasibility of creating a state park on the North and South Forks of the Mayo River in Henry County ([VADCR 2007](#)). Investments in land and facilities are an identified need and interstate connectivity of park lands and waters would increase both the recreational and ecological impact of these investments.

Conservation contributing to this alternative includes the following recent acquisitions. Duke Energy funded the acquisition of the 340.317 acre Lower Trust Parcel, including the corresponding 3 miles of river corridor, and transferred title to North Carolina State Parks for long term stewardship and conservation in perpetuity as part of the Mayo River State Park. Duke Energy funded the acquisition of 214 acres of real property along the Mayo River in Henry County, VA, and transferred title to VADCR for long-term stewardship and conservation in perpetuity as part of Virginia's Mayo River State Park.

This alternative includes additional Mayo River land conservation up to 64.403 acres of floodplain and riverbank land along the Mayo River and conveyance of ownership of the land to the State of North Carolina for conservation as part of North Carolina's Mayo River State Park. The State will manage the property for long term stewardship and conservation in perpetuity. Conservation of such property within the state park system of North Carolina provides ecological and recreational benefits: preserving high-quality habitat for threatened or rare terrestrial and aquatic species, and providing public access and recreational opportunities for anglers, hikers, paddlers, and other outdoor recreationists.

The Environmental Assessment only applies to the not yet completed portion of Alternative 2 (i.e., acquisition and conveyance to the State of North Carolina of approximately 64.403 acres total of Mayo River riverplain and floodplain to be managed for long term stewardship and conservation in perpetuity). This action is a preferred alternative for this Draft RP/EA because it meets the all criteria identified by the Trustees for a good restoration project to address the injuries caused by the Spill. This alternative is expected to increase habitat quality and quantity, promote habitat connectivity, create new public use opportunities, and benefit public natural resources within the Dan River watershed. Acquisition and conservation of floodplain and riverbank properties along the Mayo River will protect miles of significant river habitat with at risk, rare and/or endangered aquatic species, adding greater access for the public to river-based recreation.

Alternative 3 - Abreu Grogan Park Improvements (preferred)

The three acre Abreu Grogan Park in Danville, VA (Pittsylvania County) is the only access to the 14-mile section of the Dan River designated as a Virginia Scenic River. As described above in Section 1.3, Abreu Grogan Park was closed April 1 - August 1, 2014 during the response to the Spill as it was used as a staging ground for removal of coal ash and contaminated sediment from Dan River. Improvements intended to add amenities to Abreu Grogan Park and increase recreation access to the river and use of the park by a broader population have been completed by Duke Energy and are detailed in Appendix A. New amenities include a courtesy dock, a fishing platform, a restroom building and an information kiosk. Handicapped accessible parking and sidewalks have been added to enable access to all of these park amenities. Other improvements to the park included a new headwall to stabilize the culvert, addition of rip-rap for river bank stabilization and relocation of the picnic table and grill. The park was re-opened with these completed improvements on May 26, 2016. The improvements to the park address recreational losses as a result of the closure of the park during the response effort.

Alternative 3 is a preferred alternative for this Restoration Plan because it meets the direct nexus criteria identified by the Trustees for a good restoration project. Abreu Grogan Park Improvements addresses the lost recreational opportunities when the park was closed to public use to support cleanup activities.

Alternative 4 - Pigg River Power Dam Removal (preferred)

Constructed in 1915 for power generation, the defunct Power Dam measured 25 feet high by 204 feet long and impounded 60 acre-feet of water over 25 acres. The Pigg River Power Dam Removal project is located just upstream of the Route 713 bridge over the Pigg River in Franklin, VA. The USFWS worked with the owner, Friends of the Rivers of Virginia (FORVA); Franklin County; Town of Rocky Mount; VADEQ; Virginia Department of Game and Inland Fisheries and others to remove the center section of the Power Dam. The purpose of this restoration alternative is to support recovery of the Roanoke logperch (*Rex percina*) through aquatic habitat restoration, fish passage, and restoration of aquatic connectivity within the Pigg River ecosystem. Duke Energy provided the funding to FORVA on August 23, 2016 and Power Dam breaching and removal was completed on September 27, 2016. Work related to the breaching included the cutting and removal of trees downed by down cutting of legacy reservoir sediment to prevent additional bank instability during the natural channel formation process.

This project removed the last impediment to fish passage within a 72 mile reach of the Pigg River from the headwaters downstream to Leesville Reservoir. The project restored 2.2 miles of aquatic instream habitat impounded upstream of Power Dam for the federally and state listed Roanoke logperch and other nongame and game fish such as smallmouth bass (*Micropterus dolomieu*). Another mile upstream of the impoundment for a total of 3.2 miles above Power Dam and 5 miles downstream of the Dam are in the process of being improved by the river's competency to transport sediment, increasing the complexity of instream habitat and facilitating the reestablishment of riparian vegetation. The remaining 45 mile river

segment downstream to Leesville Reservoir is also beginning to improve with regards to channel habitat, stability, and complexity through restored sediment transport capacity. In addition to on-going physical and biological monitoring, signage was constructed to provide the public assistance in interpreting the historic significance of the powerhouse and remnants of the Pigg River Power Dam. Other benefits of the project include the restoration of flood attenuation, public infrastructure protection for the Rocky Mount Wastewater Treatment Plant and the Route 713 Bridge, removal of a public safety and boating hazard, and the future establishment of a public access area and county park for recreational fishing and boating. Implications for the endangered Roanoke logperch had been extensively evaluated (USFWS 2016) and endangered species consultations and all applicable Federal, state and local regulatory reviews were completed prior to implementation. Additional details regarding the Power Dam removal and benefits are available at <https://www.fws.gov/northeast/virginiafield/partners/powerdam.html> and are included in Appendix B.

Alternative 4 is a preferred alternative for this Restoration Plan because it meets the Trustees' restoration goals and objectives criteria identified by the Trustees for a good restoration to address the injuries caused by the Spill. Breaching the Pigg River dam restores river habitat, improves water quality, re-establishes fish movement, and enhances fishing and recreational boating opportunities.

Alternative 5: Establishment of Public Boat Launch Facilities on the Dan River (preferred)

As described in Section 1.3, the Spill caused a loss of recreation as a result of fishing closures along the Dan River during the Spill and Spill response. Additionally, public responses to the Trustee's restoration scoping indicated that limited access in the Dan River impedes recreational use and enjoyment of the resource. This alternative includes the establishment of new public access location(s) within the upper Dan River Basin to address recreational losses from the Spill by increasing the access. The boat launch(es) may accommodate either motorized or non-motorized boats. The Trustees shall identify a maximum of one motorized boat access location or a maximum of two non-motorized boat access locations.

Alternative 5 is a preferred alternative for this Restoration Plan because it meets the all criteria identified by the Trustees for good restoration to address the injuries caused by the Spill.

Alternative 6A: Rare and Nongame Species Restoration (Mussels)

The Trustees considered a proposed approach for captive propagation and release of freshwater mussels into the wild, with the goal of developing connected, self-sustaining populations in North Carolina and Virginia. The approach is intended to advance conservation of the federally endangered James spinymussel. Furthermore, while not currently listed as threatened and endangered, many non-listed "at-risk" species also are imperiled and would benefit from strategies considered. In particular, four levels of species restoration, augmentation, expansion, reintroduction, and establishment were identified. In North

Carolina, only augmentation and expansion options within the state were evaluated, whereas all levels were considered in Virginia based on existing policies and opportunities. Species experts were consulted to identify species-specific and location-specific opportunities to advance restoration options. The primary determination of a suite of species to be restored at a specific reach was based on species accounts, ability to propagate the species under captive conditions, the number of specimens available, and the current information on a species' life history.

Ultimately, while the Trustees deem a community mussel restoration approach to be both important to consider and likely to deliver substantive benefits capable of offsetting natural resource injuries, specific timing and policy considerations limited the feasibility of implementing these efforts. In particular, because of the state and federal listing status of several of the species would necessitate policy approvals and designations for which the timing and outcome were not well aligned with the restoration planning and delivery effort for the Dan River NRDAR process. Accordingly, Alternative 6A, the community mussel restoration project is not a preferred restoration alternative.

Alternative 6B: Rare and Nongame Species Restoration (Roanoke logperch)

The Roanoke logperch, a federally-endangered fish, is known from the mainstem of the Dan River upstream of the Site, as well as in two tributaries to the Dan River downstream of the Site. Historically, populations of Roanoke logperch were likely widespread throughout tributaries and the mainstem of the Dan River. Declines are attributed to sedimentation and pollution which lead to decreased water quality as well as population fragmentation from dams and other barriers to passage. Captive propagation (for which successful rearing techniques are known) and release and/or translocation of Roanoke logperch individuals into suitable habitat are tools for restoring diversity and abundance. The Trustees considered potential opportunities for Roanoke logperch restoration in North Carolina and Virginia as identified by species experts.

In Virginia, Roanoke logperch populations are generally more stable than other locations throughout the species' range; however, the addition of new individuals, and thus more genetic variation, to enhance population viability (or augmentation) is desirable. The Trustees evaluated a proposed restoration project intended to facilitate: 1) an increase in genetic diversity and the genetically effective population size within the Goose Creek population; and 2) a decrease in genetic divergence between the Goose Creek and Roanoke River populations. In North Carolina, Roanoke logperch populations are vulnerable and unstable due to low densities and both limited and fragmented range. Accordingly, based on the low density of Roanoke logperch in candidate streams in North Carolina, the Trustees evaluated a restoration approach that entailed demographic augmentation (to boost the number of individuals to achieve effective population targets) through release of captive reared individuals. Candidate sites were identified based on field-based reconnaissance and screening of candidate areas by species experts since 2009.

Like the community mussel restoration approach (Alternative 6A), the Trustees consider the restoration opportunities for Roanoke logperch that were considered to be important and meaningful in terms of the ability to offset potential natural resource injuries; however, again the timing of policy tools and other designations precluded further consideration by the DRNRTC. Furthermore, one proposed restoration alternative (Alternative 4) has been determined to provide significant uplift for the Roanoke logperch and a higher immediate priority for Roanoke logperch conservation given potential for this action to support recovery efforts for the species.

Alternative 7: Water Quality Improvements via Supplemental Support for Virginia Agricultural Cost Share Program

Watershed improvement projects to address non-point source pollution and excessive sedimentation to Virginia waterbodies have been identified via the VADCR's Division of Soil and Water Conservation. Specifically, the number of proposed cost share projects addressing Stream Exclusion with Grazing Land Management (SL-6) practices typically exceed available funding. The Trustees considered whether implementation of projects that would otherwise be unfunded could result in sediment and non-point pollution reduction sufficient to offset natural resource injuries associated with the Dan River Spill.

This alternative was not identified for further consideration at this time given that supplemental funding support for SL-6 projects has been realized via alternative funding sources (above and beyond the original cost share program).

The overall objective of the restoration process is to make the environment and public whole for injuries to natural resources and/or service losses resulting from the Spill. To meet that objective, the benefits of restoration actions must be related, or have an appropriate nexus, to the natural resource injuries and losses. To achieve this fundamental objective, the Trustees are proposing restoration alternatives 2, 3, 4 and 5 to compensate the public for the natural resource injuries and lost recreation as a result of the Spill. Each alternative was evaluated against the same restoration priorities and factors described above. The Trustees believe that these alternatives represent a cost-effective and beneficial means by which to restore or replace the injured natural resources and the services they provided. These projects have the capacity to improve water quality, to provide improved habitat for a diversity of wildlife, and to enhance the recovery of endangered and rare species. Additionally, they will provide public river access for recreational activities including bird watching, nature photography, hiking, fishing, kayaking, picnicking and other uses; and create a link between local walking/biking trails and the nearby local or state parks.

4.0 ENVIRONMENTAL ASSESSMENT

This Chapter presents pertinent information about the affected area of the preferred restoration project alternatives that have not been completed and the Trustees' analysis of the

environmental consequences of implementing those projects. The Environmental Assessment only applies to Alternative 5, Boat Ramps, and the not yet completed portion of Alternative 2, acquisition and conveyance to the State of North Carolina of approximately 64.403 acres total of Mayo River riverplain and floodplain to be managed for long term stewardship and conservation in perpetuity. Alternatives 3 and 4, and a portion of Alternative 2, have previously been implemented by Duke Energy and thus are outside the scope of this Environmental Assessment.

4.1 Affected Environment

This section presents a brief description of the physical, biological, and cultural environment for the waterways and ecosystems adjacent to and in the vicinity of the preferred alternatives. The Dan River basin encompasses 3,739 square miles and 11,123 linear stream miles within North Carolina and Virginia. The affected area includes those lands immediately adjacent to the river that would be affected by proposed boat ramp(s) and floodplain and riverbank properties along the Mayo River in North Carolina and Virginia that qualify for long term stewardship and conservation in perpetuity as part of the North Carolina and Virginia Mayo River State Parks.

4.1.1 Physical Environment

4.1.1.1 Surface Water

The Dan River flows for 50.5 miles through Stokes County, NC and 39.5 miles through Rockingham County, NC. Major tributaries entering the Dan River along this reach include the Mayo and Smith rivers. Alternative 2 includes portions of the Mayo River in Henry, VA and Rockingham County, NC. The potentially affected surface water environment, at a minimum includes, the surface water pathway in the Dan River from the point of discharge from the Facility's storm sewer management pipe in Rockingham, NC downstream (approximately 77 river miles) to and including Buggs Island Lake (John H. Kerr Reservoir), located in Virginia and North Carolina. Likewise, it also includes the surface water environment in proximity to planned future restoration projects including the mainstem Dan and Mayo Rivers upstream of the Spill site, including surface waters in the counties of Stokes and Rockingham, NC. In total, the potentially affected surface water environment encompasses waters in the counties of Rockingham, Stokes, Caswell, Person, Granville, Vance, and Warren NC and Pittsylvania, Halifax, Charlotte, and Mecklenberg VA.

The presence of impaired waters in the Dan River Basin without high levels of development indicates a historic degradation of water quality conditions in the river and its tributaries and/or persistent agricultural or forestry non-point source pollution problems (PTRC 2012a). Over 20% of the Dan River Basin's assessed waters are listed as impaired with high levels of turbidity, poor ecological habitat conditions, and low dissolved oxygen levels as leading causes. However, over half (55%) of these impaired waters in the Dan River Basin are listed as failing to meet federal water quality standards for E. coli or fecal coliform bacteria, an indication of the presence of fecal material from human, livestock, and/or wildlife sources (PTRC 2012a). There is a Total Maximum Daily Load (TMDL) for E. coli on the Dan River in Virginia that recommends

reductions in sources of up to 40% from wildlife and agricultural sources (VADEQ 2007). North Carolina has adopted a similar TMDL for fecal coliform bacteria on the Dan River Basin to address their sources of *E. coli* contributing to water quality degradation as identified and assessed by VADEQ (PTRC 2012a). North Carolina Division of Water Quality (NCDWQ) has developed a TMDL for turbidity impairments in the Dan River that has determined that reductions in non-point sources of sediment pollution will be necessary to restore supportive water quality conditions to those waters.

4.1.1.2 Regional Geology and Soils

The affected area is located in the Piedmont region of North Carolina and Virginia. The geography is rolling, gentle hills and flat valleys with elevation ranging from about 300–400 feet (90–120 meters) in the east to over 1,000 feet (300 meters) in the west. Geology and soils are characterized by the Piedmont Belt, Triassic Basin, and Milton Belt that are defined as occupying an area of rocks that have similar features and come from the same point in geologic history (PTRC 2012b). According to the 2012 Eden Area Watershed Assessment:

Soils formed from the poorly-draining sedimentary rock of the Triassic Basin overlap with the soils formed from the more porous but more erodible metamorphic rock of the Piedmont Plateau (including the Inner Piedmont, Western Piedmont and Milton Belts) creating a complex landscape. The soils derived from the Triassic Basin ecoregion tend to be high in clay with low permeability and moderate to high shrink-swell potential, such as the Clover or Mayodan soils group. Soils derived from the Triassic Basin include Ayersville (not hydric, slightly erodible), Leaksville (all hydric, moderately to highly erodible), Clover/Mayodan (not hydric, moderately erodible), Spray (not hydric, slightly erodible) and Stoneville (not hydric moderately erodible) (US Department of Agriculture [USDA], 2012). Due to weathering processes the soils derived from the Triassic Basin geology are often located on top of the ridges while the older, more erodible metamorphic derived soils exposed on the sides of the slopes. The alluvial soils along the Smith and Dan Rivers are thus formed from a weathered material from sedimentary, igneous and metamorphic rock from surrounding uplands. The soil composition of the watershed ensures that the receiving waters will be extremely prone to sediment pollution.

4.1.1.3 Climate

Climate is humid subtropical characterized by mild winters, long pleasant periods of spring and fall, and warm summers. Average annual temperature is 59 degrees, average annual rainfall is 41 inches, and average annual snowfall is 8 inches.

4.1.2 Biological Environment

4.1.2.1 Terrestrial and Aquatic Habitat

The upper portion of the Dan River basin in North Carolina (including the Dan River mainstem) is primarily forested, but a significant portion is also in use as cultivated cropland and pasture (PTRC 2012). The affected area is typically characterized by a low slope freshwater perennial river channel containing a heterogeneous substrate of sand, gravel, and cobble bordered low banks of riparian forests that grade up into upland or floodplain hardwood forests, depending

on valley type and slope. Less than 50% of the floodplains have been converted to agriculture or pasture. Natural Heritage inventories conducted in Stokes and Rockingham, NC were able to identify nineteen unique natural areas that are significant on the regional, state and national level. These characteristics and relatively low human disturbance levels maintain high biological diversity and ecological function from natural resources in the Dan River Basin.

4.1.2.2 Fish and Wildlife

A variety of endemic game and non-game mammals, birds, reptiles, amphibians, invertebrates, freshwater fish, crustaceans and fresh water mussels occur in the Dan and Mayo River basins. Wildlife species known to occur within the Roanoke River basin, of which the Dan and Mayo rivers are a part of, includes 18 mammal species, 41 species of amphibians/reptiles, and 143 species of birds. Wildlife in the vicinity of the proposed Mayo River conservation project include managed small and large game species, such as white tailed deer and wild turkey, and non-game species common to the region, including a variety of non-game animals, such as mussels, amphibians, aquatic invertebrates and upland, riparian, and wetland birds. Fishing pressure is relatively light, but fishing opportunities exist for sunfish, largemouth bass, smallmouth bass and catfish.

Common game animals include black bear (*Ursus Americanus*), white-tailed deer (*Odocoileus virginianus*), wild turkey (*Meleagris gallopavo*), American crow (*Corvus brachyrhynchos*), groundhog (*Marmota monax*), ruffed grouse (*Bonasa umbellus*), northern bobwhite (*Colinus virginianus*), common pheasant (*Phasianus colchicus*), rabbit (*Oryctolagus cuniculus*), the grey (*Sciurus carolinensis*), red (*Tamiasciurus hudsonicus*), and fox squirrel (*Sciurus niger*), migratory waterfowl, bobcat (*Lynx rufus*), coyote (*Canis latrans*), fox (*Vulpes vulpes*), opossum (*Didelphis virginiana*), skunk (*Mephitis mephitis*), beaver (*Castor canadensis*), and raccoon (*Procyon lotor*). Game fish in inland waters comprise more than 29 species that include black bass (largemouth [*Micropterus salmoides*], smallmouth [*Micropterus dolomieu*] and spotted [*Micropterus punctulatus*]), crappie (white [*Pomoxis annularis*] and black [*Pomoxis nigromaculatus*]), Sunfish (bluegill, [*Lepomis macrochirus*] redbreast sunfish [*Lepomis auritus*], redear sunfish [*Lepomis microlophus*], pumpkinseed [*Lepomis gibbosus*], warmouth [*Lepomis gulosus*], green sunfish [*Lepomis cyanellus*], Roanoke bass [*Ambloplites rupestris*], rock bass [*Ambloplites rupestris*], flier [*Centrarchus macropterus*], and all other species of the family Centrarchidae), Mountain trout (including but not limited to brook [*Salvelinus fontinalis*], brown [*Salmo trutta*] and rainbow trout [*Oncorhynchus mykiss*]), Kokanee salmon (*Oncorhynchus nerka*), walleye (*Sander vitreus*), sauger (*Sander canadensis*), pickerel (chain [*Esox niger*] and redbreast [*Esox americanus*]), muskellunge (*Esox masquinongy*), white bass (*Morone chrysops*), Bowfin (*Morone saxatilis* x *Morone chrysops* - striped bass hybrid), striped bass (*Morone saxatilis*), shad (American [*Alosa sapidissima*] and hickory [*Alosa mediocris*]), white perch (*Morone americana*), yellow perch (*Perca flavescens*), spotted sea trout (*Cynoscion nebulosus*), flounder (*Paralichthys dentatus*), red drum (*Sciaenops ocellatus* - channel bass, red fish and puppy drum) and the endemic Cape Fear shiner (*Notropis mekistocholas*).

A portion of the 76 species of reptiles and 96 species of amphibians known in North Carolina occur in the Dan and Mayo River basins. Bird species that frequent the area include American

goldfinch (*Carduelis tristis*), Canada goose (*Branta canadensis*), great blue heron (*Ardea herodias*), osprey (*Pandion haliaetus*), northern cardinal (*Cardinalis cardinalis*) and many other songbirds common to the eastern US. A few examples of amphibians and reptiles common to the area are green frog (*Rana clamatans*), American toad (*Bufo americanus*), copperhead (*Agkistrodon contortrix*), black racer (*Coluber constrictor*), Eastern box turtle (*Terrapene carolina*) and yellow-bellied slider (*Trachemys scripta scripta*) (Van Alstine et al. 1999).

4.1.2.3 Rare, Threatened, Endangered, and Special Concern Species

The Dan and Mayo River basins provide habitat for rare and endangered plants, animals and aquatic organisms. Six federally listed species occur within the Affected area and 79 species of plants and 55 species of insects, birds, amphibians and reptiles, fish, mussels, and mammals that are considered rare, threatened, endangered or of special concern were identified by the USFWS' Information, Planning and Conservation System (IPaC 2018) and the North Carolina Natural Heritage Data Explorer (2018) (Appendix C). Federally listed species include the Northern long eared bat (*Myotis septentrionalis*), James spinymussel (*Pleurobema collina*), Roanoke logperch (*Rex percina*), Schwenitz's sunflower (*Helianthus schweinitzii*), small-anthered bittercrest (*Cardamine micranthera*) and smooth coneflower (*Echinacea laevigata*). USFWS Birds of Conservation Concern in the vicinity of the Mayo River Conservation project include bald eagle (*Haliaeetus leucocephalus*), eastern whip-poor-will (*Antrostomus vociferous*), Kentucky warbler (*Geothlypis formosa*), prairie warbler (*Dendroica discolor*), prothonotary warbler (*Protonotaria citrea*), red-headed woodpecker (*Melanerpes erythrocephalus*), rusty blackbird (*Euphagus carolinus*), and wood thrush (*Hylocichla mustelina*).

4.1.3 Socioeconomic and Cultural Environment

4.1.3.1 Demographics

The Dan and Mayo River basins are primarily rural, with less than five percent of land mass having seen city or town development (DRBA 2018). The counties in the proposed action area have experienced little growth in recent years. Rockingham (population 90,949 in the 2017 census) and Stokes (population 45,717) are characterized by relatively comparative poverty rates (18.1 and 12.4%) to the State average (15.4%) (USCB, 2018). The population growth has been more rapid to the south of Rockingham County (i.e., northwest Guilford County) while negative growth rates are common in the Virginia counties in the northern portion of the affected area (Rockingham County 2010). Incorporated human settlements include Danbury, Walnut Cove, Pine Hall, Madison, Mayodan and Eden.

4.1.3.2 Recreation

Local, state, and national parks and recreation areas existing in or near the Affected area include Hanging Rock State and Mayo River State Parks in North Carolina and Philpott Lake, Fairystone State Park, the Blue Ridge Parkway and Rocky Knob National Recreation Area in Virginia. Counties and municipalities have embraced efforts to create recreational amenities that highlight the unique heritage of the area and networks of Greenways and Blueways have been planned and established throughout the basin. Examples are the Richmond & Danville Rail Trail in Pittsylvania County and the Dick & Willie Passage in Martinsville/Henry County on the

route of the old Danville & Western Railroad. The number of river access points on the Dan and its tributaries has greatly increased, providing more opportunities for fishing and boating enthusiasts and several commercial outfitters offer guided and self-guided trips. Prior to 2002, only one river access on the Smith River in Henry County existed, today there are eight. The basin offers paddlers fast-moving white-water runs of the Dan River in Kibler Valley or slow, relaxing floats as the Dan crosses the Virginia/North Carolina border- where historic batteau navigation structures make it easy to paddle the rivers even in low water (DRBA 2018). The many lakes and reservoirs of the basin serve as attractions for outdoor enthusiasts who enjoy fishing, paddling or wildlife viewing. The North Carolina Mountains-to-Sea Trail and the Virginia Beaches to Bluegrass Trail provide hikers and cyclists a contiguous off-road path from the Blue Ridge Mountains to the Atlantic Ocean (PTRC 2012).

4.1.3.3 Cultural and Historic Resources

Aside from plant and animal habitat, the Dan River Basin also supports a culture that has been historically rich in farming and forestry. Tobacco was an important cash crop in the area; the Brightleaf tobacco curing process originated in Caswell County, bringing great wealth to the area. Prior to the Civil War, Caswell was one of the wealthiest counties in North Carolina as evident by its significant collection of antebellum homes. In the late 18th century and early 19th century, transportation was largely by water. Improvement of the river for batteau navigation spurred economic development and the founding of South Boston and Danville, VA and Milton, Leaksville (Eden) and Madison, NC. Railroads arrived in the mid-19th century, connecting the basin to wider commerce and bringing tobacco marketing and manufacturing to the towns. The railroads also made timber production more viable and companies moved in to harvest timber from the Basin, which was used to meet demand in the Northeastern and Midwestern U.S, where forest resources had been greatly depleted. While forestry still plays an important role in economy of the Basin, the advent of companies like R.J. Reynolds and American Tobacco Company meant the consolidation of small farms and factories. With the decrease in tobacco farming came the proliferation of furniture and textile industries. Cities like Bassett, Martinsville, Danville, Eden and Roxboro saw an industrial boom; however, many of these jobs would be outsourced globally beginning in the 1970s. This decline in manufacturing led to a major economic slump and the move toward more diverse industries.

4.2 Environmental Consequences of the No Action Alternative and Preferred Alternatives

NEPA requires that a federal agency evaluate the potential impacts of its proposed actions. This includes evaluation of what would happen if the Trustees did nothing further, referred to as the “No Action Alternative”. This section of the Draft RP/EA sets out the potential impacts of both the No Action Alternative and the two restoration type alternatives evaluated and identified as preferred in Chapter 3 as meeting the Trustees’ Restoration Evaluation Criteria. The analysis presented here considers the range of potential environmental consequences that may be anticipated to occur as a result of implementation of activities within the scope of the Preferred Alternatives.

The following definitions are used in this section to characterize the nature of the various impacts evaluated in this Draft RP/EA:

- Short-term or long-term impacts. These characteristics are determined on a case-by-case basis and do not refer to any rigid time period. In general, short-term impacts are those that would occur only with respect to a particular activity or for a finite period. Long-term impacts are those that are more likely to be persistent and chronic.
- Direct or indirect impacts. A direct impact is caused by a proposed action and occurs contemporaneously at or near the location of the action. An indirect impact is caused by a proposed action and might occur later in time or be farther removed in distance but still be a reasonably foreseeable outcome of the action. For example, a direct impact of erosion on a stream might include sediment-laden waters in the vicinity of the action, whereas an indirect impact of the same erosion might lead to lack of spawning and result in lowered reproduction rates of indigenous fish downstream.
- Minor, moderate, or major impacts. These relative terms are used to characterize the magnitude of an impact. Minor impacts are generally those that might be perceptible but, in their context, are not amenable to measurement because of their relatively minor character. Moderate impacts are those that are more perceptible and, typically, more amenable to quantification or measurement. Major impacts are those that, in their context and due to their intensity (severity), have the potential to meet the thresholds for significance set forth in CEQ regulations (40 CFR § 1508.27) and, thus, warrant heightened attention and examination for potential means for mitigation to fulfill the requirements of NEPA.
- Adverse or beneficial impacts. An adverse impact is one having adverse, unfavorable, or undesirable outcomes on the man-made or natural environment. A beneficial impact is one having positive outcomes on the man-made or natural environment. A single act might result in adverse impacts on one environmental resource and beneficial impacts on another resource.

4.2.1 Environmental Consequences of the No Action Alternative

NEPA requires a federal agency to consider a “no action” alternative. Under this alternative, the Trustees would take no direct action to restore injured natural resources or compensate for lost services pending natural recovery. Instead, the Trustees would rely on natural processes for recovery of the injured natural resources and their associated services. While natural recovery would occur over varying time scales for the injured resources services, the interim losses suffered would not be compensated under the “no action” alternative.

The principal advantages of this approach are the ease of implementation and low cost. This approach relies on the capacity of ecosystems to “self-heal.” CERCLA, however, establishes

Trustee authority to seek compensation for interim losses pending recovery of the natural resources. Further, lost ecosystem services during the “self-heal” period would not be addressed under this approach. The “no action” alternative is rejected for compensatory restoration, as it does not meet the purpose and need for action. Losses were suffered and impacts continue during the period of recovery from the Spill. Technically feasible, cost-effective alternatives exist to compensate for these losses.

4.2.2 Environmental Consequences of the Preferred Alternatives

A summary of environmental consequences of the preferred Alternatives is provided in Table 2. In general, adverse impacts associated with implementation of Alternative 2 are anticipated to be minor and temporary. Outside of minor and mostly temporary adverse impacts during construction, implementation of Alternative 5 is anticipated to provide benefits, primarily in the form of improved recreational access to the upper Dan River.

4.3 Summary of Cumulative Impacts

The Council on Environmental Quality’s (CEQ) regulations to implement NEPA require the assessment of cumulative impacts in the decision-making process for federal projects, plans, and programs. Cumulative impacts are defined as “the impact on the environment which results from the incremental impact of the action when added to other past, present, and reasonably foreseeable future actions regardless of what agency (federal or non-federal) or person undertakes such other actions” (40 C.F.R. §1508.7). As stated in the CEQ handbook, “Considering Cumulative Effects” (CEQ, 1997), cumulative impacts need to be analyzed in terms of the specific resource, ecosystem, and human community being affected and should focus on effects that are truly meaningful. The cumulative effects analysis of the preferred alternatives in this Draft RP/EA is commensurate with nature and the degree of direct and indirect effects anticipated from implementation of the projects. For the purpose of this analysis, the cumulative impact spatial boundary includes the upper Dan River Basin, shown in Figure 1, since that is where projects described would occur. The preferred alternatives being evaluated in this Environmental Assessment are anticipated to result in predominantly beneficial impacts to recreational uses, with potential minor benefits to riverine and riparian habitat as a result of conservation activities at the Mayo River conservation site.

Implementing the alternatives as proposed and analyzed in this Draft RP/EA would have no major adverse impacts on upper Dan River Basin habitats, on adjacent lands and waterways, or on the natural resources within each. As described above, the proposed projects may result in minor, short term adverse impacts and both short- and long-term beneficial impacts. When considered with other past, present, and reasonably foreseeable future actions within the upper Dan River Basin, the preferred alternatives are not anticipated to have adverse cumulative impacts. Direct and indirect adverse impacts, as discussed previously, are likely to be short term and will occur primarily during periods of active construction activities. Periods of active construction for one or more boat ramps are anticipated to be less than one month, and individually and cumulatively, would result in only short-term impacts. The Preferred Alternatives are not expected to result in significant cumulative impacts on the human

environment since they alone, or in combination with other current and future activities (described below) in the vicinity, would not significantly change the larger current hydrological patterns of discharge, recreational use, economic activity or land-use in the upper Dan River Basin.

Other activities in the upper Dan River Basin that may be undertaken by other entities, private and public, vary widely. However, the Dan River Basin is largely rural and has experienced little growth and development in recent years. Activities on private parcels may include maintenance of utilities, development of housing on nearby or adjacent uplands, and/or agriculture practices on adjacent uplands. These types of activities are expected to result in short- and long-term adverse impacts within the upper Dan River Basin. Maintenance of public utilities, such as power lines, and pipelines in easements within state or federally-owned lands will not be impeded as a result of the Preferred Alternatives. State agencies may undertake land or wildlife management activities on parcels under their control throughout the project area. These activities may include restoration activities similar to those proposed under this Draft RP/EA and others such as road maintenance. These activities would result in both short- and long-term adverse and beneficial impacts.

Table 2. Summary of Environmental Consequences of the No Action and Preferred Alternatives.

Environmental Consequences	Alternative 1: No Action	Preferred Alternatives	
		Alternative 2 – Remaining Mayo River Conservation	Alternative 5 - Establishment of Public Boat Launch Facilities on the Dan River
Physical Resources			
Hydrology and Water Quality	Project area water, air, and geological/sediment conditions would not be affected since no restoration would occur.	Long-term, indirect, minor and beneficial impacts since conservation activities could enhance habitat quality and return to natural conditions. Increase human use could result in increased trash in waterways.	Short-term, minor, direct and localized impacts to water quality could occur during construction. Construction activities could increase turbidity in the immediate project vicinity, although best management practices (BMPs) would minimize impacts.
Air Resources	Any ecological benefits that may result from Alternative 2 would not occur, and the trajectory of any ecologically degraded areas would remain unchanged.	No impact to local or regional air quality is expected.	Short-term, direct, minor, and adverse impacts during construction as a result of heavy equipment emissions and dust.
Sediment/ Geology		Conservation activities have potential to maintain or enhance natural conditions over time. Improved sediment transport and surface runoff following conservation activities could improve aquatic habitat. Impacts are expected to be long-term, indirect, minor and beneficial.	Minor permanent impacts to habitat within the boat ramp footprint area and immediately adjacent to the ramp would occur. Localized disturbance of sediments during boat ramp construction is anticipated.
Biological Resources			
Fish and Wildlife	Project area fish, wildlife, vegetation, and special species would not be affected since no restoration would occur.	Long-term minor benefits to fish and wildlife are anticipated since the acquired land will be removed from development or conversion pressure and management can be implemented to control invasive species or complete other activities beneficial to fish and wildlife.	Short-term, direct, and minor adverse impacts to fish and other aquatic biota during construction due to increased turbidity and sedimentation from excavation. BMPs would be employed to reduce impacts.

Table 2 Continued

Environmental Consequences	Alternative 1: No Action	Preferred Alternatives	
		Alternative 2 – Mayo River Conservation	Alternative 5 – Establishment of Public Boat Launch Facilities on the Dan River
Biological Resources (cont.)			
Vegetation	Project area fish, wildlife, vegetation, and special species would not be affected since no restoration would occur. Any biological improvements that may occur from Alternative 2 would not be realized	Long-term, indirect, and minor benefits to vegetation are expected because habitats would be conserved and potentially enhanced, including control of invasive species.	Construction activities such as clearing and earth moving would directly impact plants within the boat ramp footprint. Affected vegetation adjacent to the construction area may be disturbed, but effects are likely to be short-term.
Special Status Species		Same consequences as listed for Fish and Wildlife	No impacts are anticipated. A survey will be completed to ensure no special status species are present. Appropriate permits or permissions would be sought, if necessary.
Socio-economics			
Economic	Project area socio-economic variables would not be affected since no restoration would occur. Potential economic benefits as a result of the enhanced recreational opportunities would not be realized.	Permanent public open space areas may have the effect of increasing nearby residential land values, and increases in recreational activity on the acquired land may result in increased economic activity. Thus, the economic impacts are expected to be long-term, direct and indirect, minor and beneficial.	Except for the resources necessary to plan, construct, and maintain the boat ramp, there are no economic impacts associated with this project.
Aesthetics and Noise		Minor long-term benefit to aesthetic and scenic qualities and values associated with acquired lands since they will be conserved. There may be a minor increase in traffic and/or recreational noise due to increased human use.	Minor, temporary, and adverse impact to aesthetics are expected during construction. Minor to moderate and temporary increase in noise is anticipated during construction.

Table 2 Continued

Environmental Consequences	Alternative 1: No Action	Preferred Alternatives	
		Alternative 2 – Mayo River Conservation	Alternative 5 – Establishment of Public Boat Launch Facilities on the Dan River
Socio-economics (cont.)			
Recreation	Project area socio-economic variables would not be affected since no restoration would occur. Recreational benefits would not be realized since access opportunities would not be created.	New or improved access to river and riparian habitat are expected. Resource-based recreational activities, such as for bird watching, canoeing, kayaking, fishing, and other similar activities, may result from this alternative.	Users of small power boats, kayaks and other small water craft are expected to benefit from one or more boat ramps along the Dan River.
Transportation		Increased traffic in the vicinity of acquired area could be minor to moderate if recreational access is enhanced. Although uncertainty remains until state park management identify specific actions, impacts are anticipated to be long-term, indirect, minor and adverse.	A minor and permanent increase in traffic in the vicinity of one or more boat ramps is possible since recreational access would be enhanced. A minor and short-term increase in contractor vehicles would occur at construction site(s).
Cultural and Historical		The potential for impacts to historic and cultural resources is very location-dependent. Activities will be subject to review under Section 106 of the National Historic Preservation Act of 1966.	Same evaluation as for Alternative 2.

Table 2 Continued

Environmental Consequences	Alternative 1: No Action	Preferred Alternatives	
		Alternative 2 – Mayo River Conservation	Alternative 5 – Establishment of Public Boat Launch Facilities on the Dan River
Socio-economics (cont.)			
Public Health and Safety	Public health and safety would not be impacted since no restoration activities would be undertaken.	Land acquisition and conservation poses no health and safety risk. Improvements to the acquired land may result in improved safety conditions at the park.	There are no anticipated impacts to public health and safety as a result of constructing one or more boat ramps.
Environmental Justice	Project area socio-economic variables would not be affected since no restoration would occur.	The project, in general, does not create a disproportionately high or adverse effect on any minority or low-income populations. An increase in public use of the newly acquired land could result in downstream economic activity in the project area and thus be generally beneficial to local economies.	Environmental justice communities will not be negatively impacted through this project. This project will create recreational benefits along the Dan River to area residents.

5.0 PROJECT FULFILMENT AND MONITORING

As described earlier, Duke Energy has completed several of the preferred restoration alternatives. Summaries of some of the completed restoration are included as Appendices to this Restoration Plan. Appendix A includes photo documentation of completed restoration of proposed Alternative 3, Abreu Grogan Park Improvements. Appendix B includes photo documentation of proposed Alternative 4, the Pigg River Dam Removal Project.

Monitoring activities for the Pigg River Dam Removal project are detailed below:

Photographic documentation of project activities occurred throughout construction. Qualitative and quantitative monitoring, which began November 2016, will be conducted annually for a period not to exceed 5 years post-construction. The purpose of monitoring is to evaluate project stabilization and inform future natural resources management decisions.

Stabilization metrics include the formation of stable channel morphology up to 3.2 miles upstream and 5 miles downstream of the dam that consists of riffles, pools, bars, benches, banks vegetated above high water level, deposition, instream habitat, mobilization of sediment, and fish passage. Initial monitoring and subsequent site visits have indicated that these metrics already indicate channel morphology downstream is transitioning to more stable riverine configuration. Once downcutting and transport of legacy sediments is completed, the upstream reach is also anticipated to reach equilibrium.

Pursuant to the Consent Decree, Duke Energy will submit semi-annual reports to the Trustees on its progress to complete the remaining preferred restoration alternatives, a portion of Alternative 2, and Alternative 5, if selected.

6.0 REFERENCES

Alderman, John M. and Joseph D. Alderman. 2014. Dan River Mapping, Habitat Assessments, and Mussel Surveys. Prepared for the Duke Energy Corporation. November 26. Pittsboro, NC: Alderman Environmental Services, Inc.

Altinakar, Mustafa. 2015—“Sediment Transport Model of Coal Ash Deposition in the Dan River from February 9, 2014 Coal Ash Spill at Duke Energy’s Dan River Station.” University of Mississippi National Center for Computational Hydroscience & Engineering.

Dan River Basin Association (DRBA). 2018. Dan River Basin Overview. Available http://www.danriver.org/content/danriver/uploads/PDF/basin_overview_final.pdf. (Accessed: 8/31/2018).

Dan River Natural Resource Trustee Council (DRNRTC). 2014a. Pre-Assessment Screen Determination for Dan River Coal Ash Spill in North Carolina and Virginia. March. 19 pp. Available https://www.cerc.usgs.gov/orda_docs/CaseDetails?ID=984. (Accessed: 10/30/2018).

Dan River Natural Resource Trustee Council. 2014b. Dan River Coal Ash Release Natural Resource Damage Assessment and Restoration: Scoping Document for Restoration Planning for Public Review and Comment. October. 26 pp. Available https://www.cerc.usgs.gov/orda_docs/CaseDetails?ID=984. (Accessed: 10/30/18).

Dan River Natural Resource Trustee Council. 2014c. List of Restoration Project Proposals Submitted by Public in Response to the Dan River Coal Ash Release Scoping Document for Restoration Planning. December. 3 pp. Available https://www.cerc.usgs.gov/orda_docs/CaseDetails?ID=984. (Accessed: 10/30/2018).

Dan River Natural Resource Trustee Council. 2015. Dan River Natural Resource Damage Assessment Plan. Available: https://www.cerc.usgs.gov/orda_docs/DocHandler.ashx?task=get&ID=1555. (Accessed: 9/22/2017).

HDR. 2015. Dan River Steam Station Coal Ash Release Summary of Environmental Data Representing Conditions Pre- and Post- Coal Ash Release. 146 pp. September.

North Carolina Department of Health and Human Services (NCDHHS). 2014. Current Fish Consumption Advisories for North Carolina. Available <http://epi.publichealth.nc.gov/oeefish/advisories.html#D>. (Accessed: August 22, 2014).

North Carolina Department of Health and Human Services. 2017. Current Fish Consumption Advisories for North Carolina. Available <http://epi.publichealth.nc.gov/oeefish/advisories.html>. (Accessed: October 11, 2017).

North Carolina Natural Heritage Data Explorer. 2018. (<https://ncnhde.natureserve.org/>). (Accessed: 9/24/2018).

Piedmont Triad Regional Council (PTRC). 2012a. Dan River Basin Watershed Prioritization Report. With support from North Carolina Division of Water Quality 205(j)/604(b) program. 86 pp.

PTRC. 2012b. Eden Area Watershed Assessment. 159 pp.

Rockingham County. 2010. A Land Use Plan for Managing Growth: Rockingham County, North Carolina. Available <http://www.co.rockingham.nc.us/pview.aspx?id=14918>. (Accessed: 8/31/2018).

U.S. Census Bureau (USCB). 2018. Quick Facts Rockingham County, North Carolina; North Carolina. Available <https://www.census.gov/quickfacts/fact/table/rockinghamcountynorthcarolina,nc/PST045217>. (Accessed: 8/31/2018).

U.S. Census Bureau. 2018. Quick Facts Stokes County, North Carolina; North Carolina. Available <https://www.census.gov/quickfacts/fact/table/stokescountynorthcarolina/PST045217>. (Accessed: 8/31/2018).

U.S. Fish and Wildlife Service (USFWS). 2018. Information, Planning and Conservation System (<http://ecos.fws.gov/ipac/>). (Accessed: 9/25/2018).

USFWS. 2016. Pigg River Restoration at Power Dam, Franklin County, VA, Project #2015-F-2742. Virginia Field Office, Gloucester, VA. Available http://www.fws.gov/northeast/virginiafield/pdf/PARTNERS/power_dam/Website%20Posts/2016_Power_Dam_biological_opinion.pdf. (Accessed: 1/18/ 2016).

Van Alstine, N.E., G.P. Fleming, and H.E. LeGrand Jr. 1999. *A Natural Heritage Inventory of John H. Kerr Reservoir, Virginia and North Carolina*. Natural Heritage Technical Report 99-07. Raleigh, NC: Virginia Department of Conservation and Recreation, Division of Natural Heritage, Richmond, VA, and North Carolina Department of Environment, Health and Natural Resources, North Carolina Natural Heritage Program.

Virginia Department of Conservation and Recreation (VADCR). 2007. Feasibility Study for a State Park on the Mayo Rivers in Henry County and Mayo Scenic Rivers Study Henry County, Virginia. Prepared by the Virginia Department of Conservation and Recreation for the Governor and the General Assembly of Virginia. Richmond, VA. 49 pp.

Virginia Department of Health. 2014. Coal Ash Release Fact Sheet. Available <http://www.vdh.virginia.gov/CoalAsh.pdf>. (Accessed: August 27, 2014).

APPENDICES


APPENDIX A: Abreu Grogan Park Amenity Summary

ABREU-GROGAN PARK

AMENITY SUMMARY

EXISTING AND PROPOSED AMENITY ENHANCEMENTS

Abreu-Grogan Park
2020 Memorial Drive
Danville, VA 24541



ENHANCEMENTS COMPLETED MAY 26, 2016




EXISTING AMENITIES AND NEW AMENITY ENHANCEMENTS WITH DESCRIPTIONS WHERE APPLICABLE

Picture 1: Existing floating dock and canoe launch. No enhancements planned.**Picture 2:** Added accessible parking and accessible sidewalk leading to the floating dock and canoe launch. Accessible sidewalk also leads to kiosk and courtesy dock.


Picture 3: Added new accessible kiosk.

Enhanced Condition


Picture 4: Added new accessible sidewalk leading to the kiosk and courtesy dock.

Enhanced Condition

Picture 5: Existing parking spaces for the floating dock and canoe launch. Accessible sidewalk to be added. Future kiosk to be added in the vicinity of the existing trash can.



Picture 6: Additional view of accessible parking and accessible sidewalk leading to the existing floating dock and canoe launch along with accessible sidewalk leading to the kiosk and courtesy dock.



Picture 7: Existing culvert to receive new headwall.**Picture 8:** New headwall added to existing culvert.

Picture 9: Existing boat ramp. Courtesy dock and connecting sidewalk to be added.



Picture 10: New accessible courtesy dock and connecting sidewalk.



Picture 11: Additional view of existing boat ramp also showing area for proposed courtesy dock and fishing platform.




Picture 12: New courtesy dock.



Picture 13: Area for proposed fishing platform and view of the existing floating dock and canoe launch.



Picture 14: New courtesy dock.



Picture 15: New accessible fishing platform.




Picture 16: Additional view of the new accessible fishing platform.



Picture 17: Existing storage building and proposed area for restroom.




Picture 18: New restroom next to the existing storage building.




Picture 19: New accessible parking spaces with accessible sidewalk connecting to the restroom and fishing platform.



Picture 20: New accessible sidewalk to the fishing platform.



Picture 21: Existing parking spaces. Portion of curb to be removed to create accessible parking for future sidewalk to connect to the restroom and fishing platform.




Picture 22: New accessible parking spaces with accessible sidewalk connecting to the restroom and fishing platform.



Picture 23: Existing picnic table and grill near the City of Danville Water Pumping Building.



Picture 24: Relocated picnic table and grill.



APPENDIX B: Pigg River Dam Restoration at Power Dam; Year 1 Monitoring Report⁸

⁸ Appendices available upon request

**AFTER ACTION REPORT
FOR
DAM BREACHING**

**Pigg River Power Dam
Franklin County, Virginia**

January 2018



Prepared by:
David Byrd
Coordinator, Virginia Partners for Fish and Wildlife Program
U.S. Fish and Wildlife Service
6669 Short Lane
Gloucester, Virginia
23061

Table of Contents

1.0 INTRODUCTION.....	3
1.1 BACKGROUND	3
1.2 COMPETED WORK.....	5
1.3 SITE DESCRIPTION	5
2.0 SITE ACTIVITIES.....	5
2.1 SITE PREPARATION.....	5
2.2 DAM BREACHING/CONCRETE REMOVAL.....	6
2.3 WOODY DEBRIS/SEDIMENT REMOVAL.....	6
2.4 RESTORATION.....	7
3.0 MONITORING	8
3.1 GENERAL.....	8
3.2 PHYSICAL.....	8
3.3 BIOLOGICAL	9
3.4 HABITAT.....	9
3.4 WETLAND.....	9
4.0 OUTSTANDING REQUIREMENTS AND RELATED FUTURE WORK	10
5.0 CONCLUSIONS	10
6.0 REFERENCES.....	11

Figure 1 – Power Dam Location Map (topographic)

Figure 2 – Power Dam Location Map (aerial)

Figure 3 – Proposed Sequential Notching and Final Notch Configuration Plan

Figure 4 –Post Construction Monitoring Locations

APPENDIX A: Photo Documentation

APPENDIX B: Year 0 and +1 Cross Sections

1.0 INTRODUCTION

1.1 BACKGROUND

Constructed in 1915 by the Rocky Mount Power and Light Company for power generation, Rocky Mount Power Dam (dam), also known as the Pigg River Power Dam, measured 25 feet (ft) high by 204 ft long (Figure 3, Photos 1, 2) and impounded 60 acre-ft of water over 25 surface acres (Figures 1, 2, Photos 1, 2). The dam was subsequently sold to Appalachian Electric Power in 1935 and decommissioned sometime in the middle 1950s.

The U.S. Fish and Wildlife Service (Service) developed an interest in removal or breaching of the dam due to the presence of the federally listed endangered Roanoke logperch (*Percina rex*). The recovery plan for the Roanoke logperch (Service 1992) lists construction of impoundments as one of the major causes for the species decline. Breaching the dam removed the last impediment to fish passage within a 75-mile reach of the Pigg River from the headwaters downstream to Leesville Reservoir, and also restored 2.2 miles of aquatic instream habitat impounded upstream of the dam for the Roanoke logperch and smallmouth bass (*Micropterus dolomieu*). Improvements to an additional mile upstream of the impoundment (for a total of 3.2 miles above the dam) and 5 miles downstream of the dam are resulting from the development of increased complexity of instream habitat, riparian vegetation establishment, and increased competency of the river to transport sediment. The remaining 45-mile river segment downstream to Leesville Reservoir are also improving with regards to channel habitat, stability, and complexity through restored continuity to the headwaters. Other benefits of the project include the restoration of flood attenuation, public infrastructure protection for the Rocky Mount Wastewater Treatment Plant and the Route 713 Bridge, removal of a public safety and boating hazard, and creating the conditions necessary for the future establishment of a public access area and county park for recreational fishing and boating.

The Service began working with the Natural Resources Conservation Service, Virginia Department of Game and Inland Fisheries, Franklin County, FishAmerica Foundation and other partners in 2005 to develop a plan for the removal of the dam. Significant progress was made in fundraising to support dam removal through Service and other partner funding. An architectural historic resource survey was conducted (Pezzoni and Associates 2007) and the dam and associated powerhouse were determined to be eligible for the National Register of Historic Places. Sediment quality and quantity sampling and analysis were completed for the legacy sediment impounded behind the dam (Froehling and Robertson 2007). While slightly elevated levels of cadmium and chromium were detected in several samples, above Threshold Effects Limits but below Potential Effects Limits, levels were insufficient to warrant concern from the Virginia Department of Environmental Quality (VDEQ) or the Service (Froehling and Robertson 2007). Pre-removal water quality sampling, a physical habitat assessment, and biomonitoring above and below the dam were completed (Hitt et al. 2009). Further efforts to study and

ultimately remove or breach the dam ceased in 2009 due to differences in partner priorities and insufficient funding.

Interest in dam removal or breaching was renewed in 2012 after a change in ownership to the Friends of the Rivers of Virginia (FORVA), a river restoration and access advocacy organization, and in 2013 following removal of Veteran's Memorial Park Dam upstream. On February 2, 2014, shortly after removal of Veterans Memorial Park Dam, an estimated 39,000 tons of coal ash spilled from a containment facility at Duke Energy's Dan River Steam Station into the Dan River in Eden, North Carolina, resulting in ash being transported over 80 miles to the Kerr Reservoir within a few days. Duke Energy began discussions with Federal and North Carolina and Virginia regulatory and natural resource agencies regarding possible voluntary restoration projects to compensate for the loss or injury to natural resources within the upper Roanoke River watershed. Duke Energy expressed interest in projects that were "shovel ready," including the Pigg River Power Dam breaching project. Duke representatives met with FORVA and other conservation partners on October 8, 2015 to discuss the project and remaining requirements for breaching or removal.

Concurrent with those activities, additional funding was provided by the Service to complete several studies needed to support removal or breaching without sediment removal. A Federal Emergency Management Agency required floodplain study was performed (Mattern and Craig 2015). The hydraulic analysis was used to determine impacts of breaching the dam on the adopted Flood Insurance Rate Maps and as a component of the input required for a sediment transport analysis to estimate the sediment transport modes and sediment loads downstream of the dam. The study indicated that removal of the dam would not result in an increase in the base flood elevation at the dam, the existing bridge located just downstream of the dam, at cross sections located downstream of the dam and bridge, and at cross sections located upstream of the dam. A geomorphic and sediment transport analysis (Kris Bass Engineering 2015) concluded in part: the Pigg River is in a disturbed state due to watershed development, human alteration, and sediment imbalances, with greater than 90% of the river downstream of the dam impacted due to sediment transport issues; a (sequential) notching strategy will not be an effective way of controlling the release of sediment and recommended a full dam breach with no notching strategy resulting in the more rapid restoration of the upstream channel and accelerating downstream recovery; the upstream channel could equilibrate in a matter of months, while downstream redistribution of sediments will continue for at least a year, with increases in sediment concentrations after storms expected for several years; and the most significant changes, including several feet of deposition, would be expected just downstream of the dam, resulting in a new baseflow channel with point bars, terraces, and new floodplains. A Memorandum of Agreement was signed among the State Historic Preservation Office (SHPO), FORVA, and the Service on May 2, 2016 authorizing impacts to the historic structure. Final regulatory permitting was completed on August 5, 2016, and SHPO approval of the intensive Phase I architectural survey was received on August 19, 2016. Fish sampling utilizing backpack electroshockers, seines, and dip nets to locate and

remove Roanoke logperch in the downstream scour hole prior to construction in compliance with the Service's October 28, 2015 non-jeopardy biological opinion for the project, was completed on August 25, 2016 (Photo 8). No logperch were collected in the scour hole, though 2 were collected in the riffle beneath the Route 712 bridge crossing. FORVA received funding from Duke Energy for the project, including monitoring, on August 29, 2016.

1.2 COMPLETED WORK

One hundred and forty ft of the upper 8.5 ft of concrete across the dam was removed to match adjacent floodplain elevations to restore flood capacity and protect and maintain riparian habitat upstream. Below this floodplain notch, 95 ft (48%) of the center of the dam was removed to restore river flow (Photo 26). The breach size and configuration was designed to match the stable channel dimension for this reach surveyed 100 yards (yd) downstream.

A section of dam 50 ft long on the north side of the Pigg River remains undisturbed to preserve and protect the power house and dam section for historic preservation and interpretation (Photo 26). A 35 ft section of the south side of the dam was also undisturbed and approximately 70% of the base of the dam remains intact (Photos 35 and 35). This approach provided for enhanced maintenance of channel stability, sediment carrying capacity and competency, and preservation of cultural resources, while achieving project goals.

1.3 SITE DESCRIPTION

The Pigg River Power Dam (Photos 1 and 2) is located on the Pigg River in Franklin County approximately 0.5 mile east of the Town of Rocky Mount, in the Piedmont region in southwestern Virginia (Figures 1-3). The dam is constructed on a bedrock outcrop 120 ft upstream of the State Route 712 (Power Dam Road) crossing of the Pigg River. Prior to breaching, the concrete gravity dam measured 25 ft high and 204 ft long, with a top width of 7 ft and a bottom width of 20 ft, not including the buttresses. Additional details of the dam and powerhouse can be found in the architectural description of the dam (Pezzoni and Associates 2007, Hill Studios 2016).

2.0 SITE ACTIVITIES

2.1 SITE PREPARATION

The contractor (Shenandoah StreamWorks LLC) began mobilizing to the site the week of August 8, 2016. Excavators equipped with both hydraulic hammers and buckets, as well as dump trucks were transported to the site. StreamWorks added No. 4 stone to the existing farm field access road leading to the site to support heavy equipment, replacing an 18 inch aluminum culvert pipe at the downslope end of the access road to provide improved drainage from the adjacent slope toward the river and installing silt fencing

(Photos 9, 16). A construction causeway/access consisting of riprap, beginning in upland under the Route 712 Bridge and terminating along the downstream face of the dam was started on August 18 and completed on August 23, 2016 (Photo 10).

2.2 DAM BREACHING/CONCRETE REMOVAL

Demolition of the dam began on August 29, 2016 (Photo 11). Initially 1 excavator with a hydraulic hammer was used to begin breaching operations. During the demolition process, concrete demolition debris was used initially to extend the work causeway along the dam face (Photo 12). After a sufficiently large platform was constructed, an additional excavator was utilized to transfer the remaining concrete rubble to the scour hole on river below the dam to form the base of the proposed wetland restoration area (Photos 13, 17, and 19). The concrete rubble utilized in the causeway widening was also placed in the scour hole prior to placement of soil and organic material within the proposed wetland restoration site. Dam breaching was completed on September 9, 2017 (Photo 19), with the exception of some remaining fine-scale concrete removal along the base of the channel breach (Photo 23), and continued through September 21, 2017, as exposed high points were removed. Approximately 715 yd³ of concrete rubble was removed during the breaching process.

2.3 WOODY DEBRIS/SEDIMENT REMOVAL

An estimated 3,000 yd³ of woody debris was located upstream of the dam (Photo 3). Quantities were based upon field observation and previous coring during sediment quantity and quality analysis. During breaching operations, the contractor began removal of the woody material to allow the river channel to return to pre-removal dimensions and completed woody debris removal after breaching was complete (Photos 13 and 15). Woody debris consisted of living trees, trunks and branches at the surface, and degraded into decomposed material at depth. Larger logs and branches were removed and stockpiled at a nearby location (Photo 16), prior to being transported offsite for disposal. Due to the degraded condition of the lower layers of woody debris, substantially less woody debris was removed than the anticipated.

Sediment and decomposed woody debris suitable for vegetation establishment were excavated behind the breach and placed in the scour hole proposed for wetland restoration area immediately downstream of the dam on river right (Photos 17 and 19).

Sediment removed behind the dam to re-establish the channel dimensions, and not utilized in the floodplain wetland restoration below the dam, remained in place to be transported by the river downstream to reestablish natural stream channel pattern; profile and dimension features including channel narrowing, riffles, pools, glides, runs and, bankfull benches (Photos 21, 26, 28, 29, 30, 35, and 36).

An unknown quantity of small and large woody debris was transported downstream during precipitation events during the breaching process and continues to be transported after project completion, as is typical with natural river channels, comprising an important component of aquatic habitat establishment (Photos 19, 21, 23, 24, 29, 30, and 35).

2.4 RESTORATION

Site restoration initially consisted of grading the proposed wetland restoration site and removal of the structural erosion and sedimentation controls. Subsequent flood flow deposition added approximately 3-4 ft of elevation to the proposed wetland restoration area, effectively precluding any potential for wetland restoration, though reestablishing a more stable floodplain elevation (Photos 25 and 26). The improved access road was left in place at the request of the Town of Rocky Mount to provide better access to the farm field adjacent to the road terminus.

During breaching operations, an area immediately upstream of the dam on river left (adjacent to the powerhouse) was identified as having a significant scour hole due to turbulent flow adjacent to the dam prior to breaching (Photo 14). Additional scouring and bank failure after breaching threatened to form a headcut into the 9-acre wetland, effectively draining it. Restoration of the slope was completed through placement of stacked stone toe protection on September 20, 2016. Backfilling the scour hole to restore a stable slope configuration, placement of coir matting, and seeding with a native seed mix was completed on September 27, 2017.

River flow mitigated restoration through channel bed and bank feature adjustment began immediately after demolition work commenced and continues to progress, particularly during high flow events (Photos 18, 20-22, 26-32, and 35-41). Natural revegetation of banks is ongoing as bank slopes stabilize.

Subsequent restoration work entailed cutting downed trees that were blocking the upstream channel in several areas and causing significant bank stress and erosion. On March 2 and July 24, 2017, work crews used chainsaws to cut tree trunks into small sections to facilitate transport downstream. This work will be ongoing as bank adjustment continues to occur through headcuts and initial channel widening, prior to channel narrowing and stabilization at the restored floodplain and stream channel elevations.

3.0 MONITORING

3.1 GENERAL

In addition to the pre-breach monitoring, qualitative and quantitative monitoring will be conducted annually for 5 years. The purpose of monitoring is to monitor the formation of stable channel morphology up to 3.2 miles upstream and 5 miles downstream of the project and inform future management decisions. Stabilization metrics include the

formation of riffles, pools, bars, benches, vegetated stream banks above ordinary high water; deposition; instream habitat; mobilization of sediment; and fish passage. A monitoring plan with methodology was submitted to interested regulatory agencies as part of VDEQ and U.S. Army Corps of Engineers permit requirements and included permanent surveyed channel cross sections, pebble counts, photography stations, sediment monitoring, and instream habitat quality assessments. Baseline studies conducted to evaluate the physical habitat, water chemistry, and biotic communities in the vicinity of the dam will be utilized for post-project monitoring. Fish sampling to determine upstream and downstream use of the restored sections of the Pigg River by Roanoke logperch and other fish species will be completed on an occasional basis. The first post-removal fish sampling occurred on August 22, 2017 (Photo 34). No Roanoke logperch were collected, though this was not unexpected given the high sediment load that continued to be transported through the restoration area. Roanoke logperch are expected to recolonize these areas once channel stability is achieved throughout the restoration reach.

3.2 PHYSICAL

Post-dam breaching monitoring by Wetland Studies and Solutions, Inc. (WSSI) began in November 2016. A total of 12 cross sections were established. Six cross sections were taken upstream, including areas far enough upstream to be beyond former backwater effects created by the dam and 6 below the breached dam downstream to where effects of the sediment transported as a result of the dam breaching were anticipated to be minimal. Spacing of the cross sections was adjusted to focus on areas around the dam where the most significant river channel and bank adjustments were expected to occur (WSSI 2016). Cross section locations were also selected to correspond with previous sediment transport and biomonitoring (Hitt et al. 2009, Kris Bass Engineering 2015).

A comparison of cross section surveys between Year 0 and 1 (Appendix B) shows slight streambed incision of approximately 1 ft at Cross Section 1, upstream of the former pool extent with increased degradation (downcutting) in Cross Sections 2-4 ranging from 2 to 7 ft at Section 4, approximately 0.8 mile upstream of the dam. Changes in channel cross sections at Sections 5 and 6 (0.37 and 0.05 mile, respectively) were less significant as a result of channel evolution that occurred between completion of dam breaching activities and post-construction monitoring when significant high flow events occurred. Colonization by herbaceous vegetation has provided stabilization in those areas where banks have ceased significant mass wasting. However, tension cracks are visible at cross sections where steep banks still exist and are exhibiting signs of mass failure (WSSI 2017).

3.3 BIOLOGICAL

Monitoring was conducted along 3 biological monitoring reaches for the project. The baseline conditions for this biomonitoring program were established by the Conservation Management Institute and the U.S. Geological Survey (Hitt et al. 2009). WSSI re-established the previously monitored biomonitoring reaches, which were monitored

October 2017 as post-construction Year 1 and will be monitored again in Year 5. Each monitoring reach was collocated with a cross section: Reach A is at Cross Section 1, Reach B is at Cross Section 7, and Reach C is at Cross Section 8. Results of benthic sampling showed a slight decrease in Stream Condition Index scores at 2 of the 3 monitoring locations (WSSI 2017) in comparison to previous monitoring results (Hitt et al. 2009). The level of variation observed from pre-removal sampling events is within the range that may be reasonably expected and attributable to independent factors such as normal climatic variation. Future monitoring events will be necessary to determine the influence of dam removal on benthic communities (WSSI 2017).

3.4 HABITAT

The stream habitat assessment by WSSI was conducted in October 2017 using guidance established in the VDEQ Standard Operating Procedures for stream habitat assessment (VDEQ 2008) and the U.S. Environmental Protection Agency's Rapid Bioassessment Protocol for habitat (Barbour et al. 1999). Habitat conditions were assessed by qualitatively rating 10 habitat parameters, including epifaunal substrate/available cover, embeddedness, velocity/depth regime, sediment deposition, channel flow status, channel alteration, frequency of riffles, bank stability, vegetative protection, and riparian vegetative zone width. The overall habitat quality of each reach was determined by adding together the individual metric scores to provide a Total Habitat Score at each reach, with a maximum of 200 points possible. Each reach was then assigned a narrative rating according to the total habitat score, where "Optimal" is 200-160, "Sub-Optimal" is 159-107, "Marginal" is 106-54, and "Poor" is 53-0. Reach A was determined to be in "Poor" condition primarily due to bank erosion with heavy deposits of material in the reach, increasing embeddedness, and resulting in an unstable substrate. Reach B was in "Marginal" condition, exhibiting moderately unstable banks with a lack of vegetation. Sediment deposition was also present in Reach B with various velocity/depth regimes and a fairly wide riparian zone. Reach C was in "Marginal" condition with moderately unstable banks, bare soil present and heavy deposition of fine material in the riverbed (WSSI 2017).

3.5 WETLAND

Hydrology, vegetation, and soil monitoring was initiated at 3 wetland sites adjacent to the former pool as a requirement of the VDEQ Water Protection Permit for the project. Moderate drought conditions were present during sampling. Soils at both Sites 3 and 4 (adjacent to Cross Section 2 and Cross Section 4, respectively) were a uniform sandy loam texture with no water or saturation observed in test pits. Two sampling locations were established at Wetland Site 2 (river left, just upstream of the dam) and hydric soil indicators were seen in both locations. No water or saturation was seen at Site 2, Point 1. Water was present at approximately 6 inches below surface elevation at Site 2 Point 2. Qualitative observations made during monthly monitoring well data collection has shown the Site 2 wetland area to be largely dry at the surface since June 2017. Wetland (hydrophytic) vegetation dominated all wetland sites (WSSI 2017).

All monitoring reports and other project related documents are available at:
<https://www.fws.gov/northeast/virginiafield/partners/powerdam.html>

4.0 OUTSTANDING REQUIREMENTS AND RELATED FUTURE WORK

In addition to the required monitoring, signage will be completed to provide the public assistance in interpreting the historic significance of the powerhouse and remnants of Pigg River Power Dam. That work is expected to be completed in 2018.

Future work at the site may include enhanced public boating and fishing access and the possible creation of a Franklin County public park.

5.0 CONCLUSIONS

The dam breaching and associated work is considered a success. The subsequent sediment transport downstream is resulting in reestablishment of more stable channel features, including channel narrowing, floodplain and inner berm benches, point bars, riffles, and pools (Photos 35 and 36). The former reservoir upstream of the dam is rapidly adjusting to a more stable channel (Photos 37-41), though complete stabilization is taking longer than anticipated in the sediment transport study and may take another year or more to fully stabilize.

6.0 REFERENCES

- Barbour, M.T., J. Gerritsen, B.D. Snyder, and J.B. Stribling. 1999. Rapid Bioassessment Protocols for use in streams and wadeable rivers: Periphyton, Benthic Macroinvertebrates and Fish, Second Edition. EPA 841-B-99-002. U.S. Environmental Protection Agency; Office of Water, Washington, D.C. 339 pp.
- Froehling & Robertson, Inc. 2007. Sediment sampling and analysis study, Pigg River Power Dam, Franklin County, VA. Report to FishAmerica Foundation, Alexandria, VA.
- Hill Studios. 2016. Phase II Survey Report, Rocky Mount Dam and Powerhouse, Franklin County, Virginia. Report to Friends of the Rivers of Virginia, Roanoke, VA.
- Hitt, N.P., J. Jones and K. Convery. 2009. Biomonitoring for the Rocky Mount Power Dam removal project: Establishing baseline conditions. Conservation Management Institute, Blacksburg, VA.
- Kris Bass Engineering. 2015. Power Dam sediment capacity and fate modeling. Report to the Service, Friends of the Rivers of VA, and Town of Rocky Mount, VA.
- Mattern and Craig. 2015. Hydraulic Analysis Summary Report Pigg River Power Dam Removal, Franklin County, VA. Report to Friends of the Rivers of Virginia, Roanoke, VA.
- Pezzoni and Associates. 2007. Rocky Mount Dam and Powerhouse (033-0016), Franklin County, Virginia, Survey Report and National Register Evaluation. Report to FishAmerica Foundation, Alexandria, VA.
- U.S. Fish and Wildlife Service. 1992. Roanoke Logperch (*Percina rex*) Recovery Plan. Newton Corner, MA. 34 pp.
- Virginia Department of Environmental Quality. 2008. Biological monitoring program quality assurance project plan for wadeable streams and rivers. Richmond, VA. 43 pp.
- Wetland Studies and Solutions, Inc. 2016. Pigg River Restoration at Power Dam, Post Construction Monitoring Report. Report to Friends of the Rivers of Virginia, Roanoke, VA.
- Wetland Studies and Solutions, Inc. 2017. Pigg River Restoration at Power Dam, Year-1 Monitoring Report. Report to Friends of the Rivers of Virginia, Roanoke, VA.

Figure 1
Power Dam Location Map




Figure 2
Power Dam Location Map





Figure 3. Proposed Sequential Notching and Final Notch Configuration Plan





Figure 4. Post Construction Monitoring Locations

APPENDIX A

Photo documentation



1. Power Dam pre-removal view southwest from Route 7124 Bridge (10/8/15)



2. Power Dam during 3 inch rainfall event, view southwest (3/16/07)



3. Woody debris upstream of Power Dam blocking river channel pre-breach, causing adjacent flooding (1/26/06)



4. Typical levee formations on both right and left banks upstream of Power Dam pre-breach (11/17/15)



5. Typical upstream river channel within pool with high levees and shallow, sediment filled channels (11/17/15)



6. Over-widened channel and scour hole on right bank below Power Dam, view east (4/16/15)



7. View north, downstream of Power Dam depicting over-widened, sediment starved channel (4/16/15)



8. Pre-breach fish sampling in the scour pool below Power Dam, view east (8/25/16)



9. Access road down to floodplain causeway with silt fencing in place, view north (9/7/16)




10. Construction access causeway in place prior to removal, view north (8/25/16)



11. Initial dam breach, view southeast (8/29/216) (credit Franklin News Post)



12. Progress of breaching activities after one day of work, view southeast (8/30/16) (credit FORVA)



13. Woody debris removal behind Power Dam breach begins, view east (9/7/16)




14. Exposure of existing scour hole (red arrow) above Power Dam, potentially leading to wetland headcut (9/7/16)



15. Removal of woody debris above Power Dam (9/9/16)




16. Woody debris stockpile area, view northwest (9/9/2016)




17. Breach nearly complete, woody debris removal continues, view southeast (9/8/16)



18. River cutting channel through relict sediment immediately upstream of breach, view east (9/12/16) (credit FORVA)



19. Fine-tuning breach opening and stockpiling of material in former scour hole to restore floodplain bench (9/12/16)



20. View southeast (upstream) of dewatering of former pool upstream of breach (9/20/16)



21. View downstream (north) from Route 712 Bridge showing channel filling and formation (9/21/16)



22. View southeast (upstream) of channel formation in former pool sediment (9/21/16) (credit FORVA)




23. Sixty-five foot width base flow channel completed through Power Dam (9/22/16) (credit FORVA)




24. View of left bank upstream of dam after stacked stone toe, backfilling, and matting stabilization (10/5/16)



25. Floodplain deposition in downstream scour area during high flow event, view southeast (11/9/16) (credit FORVA)



26. Floodplain deposition on left and right banks below breach (2/2/17)



27. Bank sloughing and new floodplain bench upstream of the breach (2/2/17)



28. Narrowing of channel and restoration of meanders downstream below Route 712 Bridge (2/2/17)



29. Cobble and gravel sediment transport through breach in dam (5/25/17)



30. Additional coarse material deposition downstream between breach and Route 712 Bridge (5/25/17)



31. Floodplain bench and channel post fallen tree removal (breach in background) (8/2/17) (credit FORVA)




32. Establishment of a meander bend and bank revegetation upstream of breach (8/2/17) (credit FORVA)



33. Narrowed channel upstream and revegetation of newly formed floodplain (8/2/17) (credit FORVA)



34. Post-removal fish sampling with VDGIF and VDOT below breach (8/22/17)



35. Riffle re-established in former scour hole below Power Dam breach (9/26/17)



36. Stable cobble/gravel point bar on the inside of a meander bend downstream of breach below Route 712 Bridge (9/26/17)



37. Re-established river channel and vegetated floodplain upstream of breach. Arrow depicts pool elevation (9/26/17)



38. River channel and floodplain approximately 580 feet upstream of breach. Arrow depicts pool elevation (10/25/17)



39. Same area from opposite side of the Pigg River illustrating high banks in area. Arrow depicts pool elevation (10/25/17)





40. Re-established river channel and vegetated floodplain 2,800 feet upstream of breach. Arrow depicts pool elevation (10/25/17)



41. Re-established meander bend and exposed rock outcrop approximately 3,100 feet upstream of breach (10/25/17)

APPENDIX B

Pre- and Post-Construction Cross Sections



PROFILE SCALE:
 HORIZ: 1"=10'
 VERT: 1"=5'
 (ELEV. RELATIVE TO ASSUMED XS END PIN AT 100.)

4400 Washington Blvd., Suite 100
 Rockville, MD 20850
 Phone: 301-477-3400 Fax: 301-477-3401
 www.wetlandinc.com

Figg River Dam Removal Restoration - Monitoring
 Rocky Mount, Virginia

Year 1 - XS 1

ELEVATION (FT)


REV	DATE	DESCRIPTION
1	10/1/2017	AS-BUILT


Projected and/or Proposed
 10/1/2017

Drawn: []
 Check: []
 Date: []


Scale: 1" = 10'

Title Block






PROFILE SCALE:
 HORIZ: 1"=20'
 VERT: 1"=10'



PROFILE SCALE:
 HORIZ: 1"=20'
 VERT: 1"=10'




5350 Highway 100, Suite 100
 Rocky Mount, VA 24156
 Phone: 757-536-0000 Fax: 757-536-0001
 www.wetland.com



Pigg River Dam Removal Restoration - Monitoring
 Rocky Mount, Virginia

Year 1 - XS 5 & 6
 07/18/2017

REV	DATE	DESCRIPTION	BY	CHKD
1	07/18/2017	AS-BUILT		

Drawn by: [blank] Date: [blank] Appraised by: [blank]
 Check: [blank] Scale: 5" = 11'
 Project: [blank]





PROFILE SCALE:
 HORIZ: 1"=10'
 VERT: 1"=5'
 (ELEV. RELATIVE TO ASSUMED XS END PIN AT 100.)

5350 Highway 100
 Rocky Mount, Virginia 24155
 Phone: 757-536-0000 Fax: 757-536-0001

Pigg River Dam Removal Restoration - Monitoring
 Rocky Mount, Virginia

Year 1 - XS 8
 Project Q-17

REVISIONS		DATE	BY	CHKD



DATE PREPARED: SCALE: AS SHOWN

Drawing and 5-copy (owner, utility and two agencies) sets

Drawn	Date	Approved

Sheet 7 of 11

Computer/Operator:



PROFILE SCALE:
 HORIZ: 1"=10'
 VERT: 1"=5'
 (ELEV. RELATIVE TO ASSUMED XS END PIN AT 100.)


5350 Highway 100
 Rocky Mount, Virginia 24155
 Phone: 757-535-0000 Fax: 757-535-0001


Pigg River Dam Removal Restoration - Monitoring
 Rocky Mount, Virginia



Year 1 - XS 9
 Sheet 0 of 7

REVISIONS		SCALE: AS SHOWN	
No.	Description	Date	By

Drawn by: _____
 Check by: _____
 Date: _____
 Scale: 8" = 11'







PROFILE SCALE:
 HORIZ: 1"=10'
 VERT: 1"=5'
 (ELEV. RELATIVE TO ASSUMED XS END PIN AT 100.)

5350 Highway 100
 Rocky Mount, Virginia 24155
 Phone: 757-536-0000 Fax: 757-536-0001

Project: Pigeon River Dam Removal Restoration - Monitoring

Location: Rocky Mount, Virginia

Year: Year 1 - NS 12

Sheet: 11 of 11

REVISIONS		DATE	BY	SCALE	REVISION

Drawn by: [] Date: []

Checked: [] Date: []

Scale: 11 = 11

APPENDIX C: List of Species classified as rare, threatened, endangered or of special concern in the Dan and Mayo River Basins. Source: U.S. Fish and Wildlife Service Information, Planning and Conservation System (IPaC) and the North Carolina Natural Heritage Program.

TAXONOMIC GROUP	SCIENTIFIC NAME	COMMON NAME	STATUS	COUNTY
Amphibian	<i>Ambystoma talpoideum</i>	Mole Salamander	Special Concern	Rockingham
Amphibian	<i>Hemidactylium scutatum</i>	Fourtoed Salamander	Special Concern	Stokes
Amphibian	<i>Plethodon wehrlei</i>	Wehrle's Salamander	Threatened	Stokes
Bird	<i>Ammodramus savannarum</i>	Grasshopper Sparrow	Watch List, Rare	Rockingham
Bird	<i>Corvus corax</i>	Common Raven	Watch List, Rare	Stokes
Bird	<i>Empidonax traillii</i>	Willow Flycatcher	Watch List, Rare	Stokes
Bird	<i>Falco peregrinus anatum</i>	American Peregrine Falcon	Endangered	Stokes
Bird	<i>Lanius ludovicianus</i>	Loggerhead Shrike	Special Concern	Rockingham
Butterfly	<i>Speyeria diana</i>	Diana Fritillary	Watch List, Rare	Stokes
Caddisfly	<i>Diplectrona metaqui</i>	a diplectronan caddisfly	Rare	Stokes
Crustacean	<i>Cambarus davidi</i>	Carolina Ladle Crayfish	Rare	Stokes
Crustacean	<i>Orconectes carolinensis</i>	North Carolina Spiny Crayfish	Special Concern	Stokes
Dragonfly or Damselfly	<i>Arigomphus villosipes</i>	Unicorn Clubtail	Watch List, Rare	Rockingham
Dragonfly or Damselfly	<i>Lestes eurinus</i>	Amber-winged Spreadwing	Watch List, Rare	Rockingham
Dragonfly or Damselfly	<i>Macromia margarita</i>	Mountain River Cruiser	Rare	Rockingham
Dragonfly or Damselfly	<i>Ophiogomphus edmunds</i>	Edmund's Snaketail	Rare	Stokes
Dragonfly or Damselfly	<i>Ophiogomphus incurvatus</i>	Appalachian Snaketail	Watch List, Rare	Stokes
Dragonfly or Damselfly	<i>Somatochlora georgiana</i>	Coppery Emerald	Rare	Rockingham
Dragonfly or Damselfly	<i>Stylurus amnicola</i>	Riverine Clubtail	Watch List, Rare	Rockingham
Freshwater Bivalve	<i>Elliptio fisheriana</i>	Northern Lance	Rare	Stokes
Freshwater Bivalve	<i>Lampsilis cariosa</i>	Yellow Lampmussel	Endangered	Rockingham
Freshwater Bivalve	<i>Lasmigona subviridis</i>	Green Floater	Endangered	Stokes

Freshwater Bivalve	<i>Pleurobema collina</i>	James Spiny mussel	Endangered	Stokes
Freshwater Bivalve	<i>Strophitus undulatus</i>	Creeper	Threatened	Rockingham
Freshwater Bivalve	<i>Villosa constricta</i>	Notched Rainbow	Threatened	Stokes
Freshwater Bivalve	<i>Villosa delumbis</i>	Eastern Creekshell	Rare	Rockingham
Freshwater Fish	<i>Ambloplites cavifrons</i>	Roanoke Bass	Rare	Rockingham
Freshwater Fish	<i>Carpionodes cyprinus</i>	Quillback	Rare	Stokes
Freshwater Fish	<i>Cottus caeruleomentum</i>	Blue Ridge Sculpin	Special Concern	Stokes
Freshwater Fish	<i>Cyprinella labrosa</i>	Thicklip Chub	Watch List, Rare	Stokes
Freshwater Fish	<i>Etheostoma flabellare</i>	Fantail Darter	Watch List, Rare	Rockingham
Freshwater Fish	<i>Etheostoma podostemone</i>	Riverweed Darter	Rare	Stokes
Freshwater Fish	<i>Etheostoma vitreum</i>	Glassy Darter	Watch List, Rare	Stokes
Freshwater Fish	<i>Exoglossum maxillingua</i>	Cutlip Minnow	Special Concern	Stokes
Freshwater Fish	<i>Moxostoma ariommum</i>	Bigeye Jumprock	Threatened	Stokes
Freshwater Fish	<i>Noturus gilberti</i>	Orange-fin Madtom	Endangered	Stokes
Freshwater Fish	<i>Percina rex</i>	Roanoke Logperch	Endangered	Rockingham
Freshwater Fish	<i>Thoburnia hamiltoni</i>	Rustyside Sucker	Endangered	Stokes
Grasshopper or Katydid	<i>Dendrotettix australis</i>	Scrub Pine Grasshopper	Watch List, Rare	Stokes
Lichen	<i>Ephebe lanata</i>	Rockshag Lichen	Rare	Stokes
Lichen	<i>Peltigera hydrothyria</i>	Waterfan Lichen	Watch List, Rare	Stokes
Liverwort	<i>Frullania plana</i>	A Liverwort	Watch List, Rare	Stokes
Liverwort	<i>Plagiochila ludoviciana</i>	A Liverwort	Rare	Stokes
Mammal	<i>Myotis lucifugus</i>	Little Brown Bat	Rare	Stokes
Mammal	<i>Perimyotis subflavus</i>	Tricolored Bat	Rare	Stokes
Mammal	<i>Sciurus niger</i>	Eastern Fox Squirrel	Watch List, Rare	Stokes
Mayfly	<i>Tsalia bernerii</i>	a mayfly	Rare	Rockingham
Moss	<i>Anacamptodon splachnoides</i>	Knothole Moss	Watch List, Rare	Stokes
Moss	<i>Andreaea rothii</i> var. <i>rothii</i>	Black Falcate Split Moss	Watch List, Rare	Stokes

Moss	<i>Brothera leana</i>	Boar Moss	Watch List, Rare	Stokes
Moss	<i>Dicranum fuscescens</i>	Fuscos Moss	Watch List, Rare	Stokes
Moss	<i>Dicranum spurium</i>	Rusty Fork Moss	Watch List, Rare	Stokes
Moss	<i>Entodon compressus</i>	Flattened Entodon	Rare	Rockingham
Moss	<i>Fissidens asplenioides</i>	A Plume Moss	Rare	Stokes
Moss	<i>Fissidens elegans</i>	A Plume Moss	Watch List, Rare	Stokes
Moss	<i>Helodium paludosum</i>	Pond Fern Moss	Watch List, Rare	Stokes
Moss	<i>Orthodontium pellucens</i>	Translucent Orthodontium	Rare	Stokes
Moss	<i>Philonotis longiseta</i>	An Apple Moss	Watch List, Rare	Stokes
Moss	<i>Polytrichum appalachianum</i>	Appalachian Haircap Moss	Watch List, Rare	Stokes
Moth	<i>Apantesis carlotta</i>	Carlotta's Tiger Moth	Watch List, Rare	Stokes
Moth	<i>Argillophora furcilla</i>	Silver Fork Cane Moth	Watch List, Rare	Stokes
Moth	<i>Caripeta aretaria</i>	Southern Pine Looper	Watch List, Rare	Stokes
Moth	<i>Catocala herodias</i>	Herodias Underwing	Rare	Stokes
Moth	<i>Chytonix sensilis</i>	Barrens Marvel	Watch List, Rare	Stokes
Moth	<i>Heliomata infulata</i>	Rare Spring Moth	Watch List, Rare	Stokes
Moth	<i>Psamatodes abydata</i>	Dot-lined Angle	Watch List, Rare	Stokes
Moth	<i>Scopula aemulata</i>	Diminutive Wave	Watch List, Rare	Stokes
Moth	<i>Ulolonche modesta</i>	Modest Quaker Moth	Watch List, Rare	Stokes
Moth	<i>Zale sp. nr. squamularis</i>	a new Zale	Watch List, Rare	Stokes
Reptile	<i>Cemophora coccinea</i>	Scarlet Snake	Watch List, Rare	Rockingham
Reptile	<i>Crotalus horridus</i>	Timber Rattlesnake	Special Concern	Stokes
Vascular Plant	<i>Agastache nepetoides</i>	Yellow Giant- hyssop	Rare	Stokes
Vascular Plant	<i>Asplenium bradleyi</i>	Bradley's Spleenwort	Rare	Stokes
Vascular Plant	<i>Baptisia albescens</i>	Thinod White Wild Indigo	Watch List, Rare	Stokes
Vascular Plant	<i>Berberis canadensis</i>	American Barberry	Special Concern	Rockingham
Vascular Plant	<i>Bromus nottowanus</i>	Nottoway Valley Brome	Watch List, Rare	Rockingham
Vascular Plant	<i>Cardamine micranthera</i>	Small-anthered Bittercress	Endangered	Stokes
Vascular Plant	<i>Cardamine rotundifolia</i>	Mountain Watercress	Threatened	Stokes
Vascular Plant	<i>Carex granularis</i>	Limestone Meadow Sedge	Watch List, Rare	Stokes
Vascular Plant	<i>Carex mitchelliana</i>	Mitchell's Sedge	Watch List, Rare	Stokes

Vascular Plant	<i>Cerastium nutans</i>	Nodding Chickweed	Watch List, Rare	Rockingham
Vascular Plant	<i>Chelone cuthbertii</i>	Cuthbert's Turtlehead	Special Concern	Stokes
Vascular Plant	<i>Corallorhiza odontorhiza</i>	Autumn Coral-root	Watch List, Rare	Stokes
Vascular Plant	<i>Crataegus succulenta</i>	Fleshy Hawthorn	Rare	Stokes
Vascular Plant	<i>Crocianthemum propinquum</i>	Creeping Sunrose	Threatened	Stokes
Vascular Plant	<i>Dichanthelium annulum</i>	Ringed Witch Grass	Rare	Stokes
Vascular Plant	<i>Dirca palustris</i>	Leatherwood	Watch List, Rare	Rockingham
Vascular Plant	<i>Echinacea laevigata</i>	Smooth Coneflower	Endangered	Rockingham
Vascular Plant	<i>Euonymus atropurpureus</i> var. <i>atropurpureus</i>	Eastern Wahoo	Watch List, Rare	Stokes
Vascular Plant	<i>Fallopia cristata</i>	Crested Climbing Buckwheat	Watch List, Rare	Stokes
Vascular Plant	<i>Fothergilla major</i>	Large Witch-alder	Rare	Stokes
Vascular Plant	<i>Gentiana austromontana</i>	Appalachian Gentian	Watch List, Rare	Stokes
Vascular Plant	<i>Gillenia stipulata</i>	Indian Physic	Threatened	Stokes
Vascular Plant	<i>Hackelia virginiana</i>	Virginia Stickseed	Rare	Rockingham
Vascular Plant	<i>Helianthus schweinitzii</i>	Schweinitz's Sunflower	Endangered	Stokes
Vascular Plant	<i>Heuchera caroliniana</i>	Carolina Alumroot	Watch List, Rare	Stokes
Vascular Plant	<i>Heuchera parviflora</i> var. <i>parviflora</i>	Grotto Alumroot	Watch List, Rare	Stokes
Vascular Plant	<i>Heuchera parviflora</i> var. <i>saurensis</i>	Sauratown Grotto Alumroot	Watch List, Rare	Stokes
Vascular Plant	<i>Heuchera pubescens</i>	Downy Alumroot	Rare	Stokes
Vascular Plant	<i>Humulus lupulus</i> var. <i>lupuloides</i>	Hops	Watch List, Rare	Stokes
Vascular Plant	<i>Humulus lupulus</i> var. <i>pubescens</i>	Hops	Watch List, Rare	Rockingham
Vascular Plant	<i>Hydrastis canadensis</i>	Goldenseal	Rare	Stokes
Vascular Plant	<i>Hydrophyllum virginianum</i>	John's Cabbage	Watch List, Rare	Rockingham
Vascular Plant	<i>Isotria verticillata</i>	Large Whorled Pogonia	Watch List, Rare	Stokes
Vascular Plant	<i>Juglans cinerea</i>	Butternut	Watch List, Rare	Stokes
Vascular Plant	<i>Juncus secundus</i>	Nodding Rush	Watch List, Rare	Rockingham
Vascular Plant	<i>Liatris aspera</i>	Rough Blazing-star	Threatened	Stokes
Vascular Plant	<i>Liatris squarrulosa</i>	Earle's Blazing-star	Rare	Stokes
Vascular Plant	<i>Lindernia monticola</i>	Flatrock Pimpernel	Watch List, Rare	Stokes
Vascular Plant	<i>Luzula multiflora</i> var. <i>multiflora</i>	Heath Woodrush	Watch List, Rare	Stokes
Vascular Plant	<i>Lysimachia tonsa</i>	Southern Loosestrife	Rare	Stokes

Vascular Plant	<i>Mertensia virginica</i>	Virginia Bluebells	Watch List, Rare	Rockingham
Vascular Plant	<i>Micranthes micranthidifolia</i>	Lettuce-leaf Saxifrage	Watch List, Rare	Stokes
Vascular Plant	<i>Mononeuria groenlandica</i>	Greenland Sandwort	Threatened	Stokes
Vascular Plant	<i>Monotropsis odorata</i>	Sweet Pinesap	Special Concern	Stokes
Vascular Plant	<i>Panax quinquefolius</i>	Ginseng	Watch List, Rare	Stokes
Vascular Plant	<i>Panax trifolius</i>	Dwarf Ginseng	Watch List, Rare	Rockingham
Vascular Plant	<i>Paronychia argyrocoma</i>	Silverling	Watch List, Rare	Stokes
Vascular Plant	<i>Parthenium auriculatum</i>	Glade Wild Quinine	Rare	Rockingham
Vascular Plant	<i>Paspalum pubiflorum</i> var. <i>glabrum</i>	Hairy-seed Crown Grass	Watch List, Rare	Stokes
Vascular Plant	<i>Pieris floribunda</i>	Fetterbush	Watch List, Rare	Stokes
Vascular Plant	<i>Pinus strobus</i>	Eastern White Pine	Watch List, Rare	Rockingham
Vascular Plant	<i>Polemonium reptans</i> var. <i>reptans</i>	Jacob's Ladder	Threatened	Stokes
Vascular Plant	<i>Polygonum tenue</i>	Glade Knotweed	Watch List, Rare	Rockingham
Vascular Plant	<i>Pseudognaphalium micradenium</i>	Small Rabbitobacco	Rare	Stokes
Vascular Plant	<i>Ptelea trifoliata</i>	Wafer-ash	Watch List, Rare	Rockingham
Vascular Plant	<i>Pyrola americana</i>	American Shinleaf	Watch List, Rare	Rockingham
Vascular Plant	<i>Quercus bicolor</i>	Swamp White Oak	Watch List, Rare	Rockingham
Vascular Plant	<i>Quercus ilicifolia</i>	Bear Oak	Endangered	Stokes
Vascular Plant	<i>Quercus muehlenbergii</i>	Chinquapin Oak	Watch List, Rare	Rockingham
Vascular Plant	<i>Rhododendron catawbiense</i>	Catawba Rhododendron	Watch List, Rare	Stokes
Vascular Plant	<i>Sceptridium jenmanii</i>	Alabama Grape-fern	Special Concern	Stokes
Vascular Plant	<i>Scutellaria serrata</i>	Showy Skullcap	Watch List, Rare	Rockingham
Vascular Plant	<i>Sedum glaucophyllum</i>	Cliff Stonecrop	Rare	Stokes
Vascular Plant	<i>Silphium connatum</i>	Virginia Cuplant	Special Concern	Stokes
Vascular Plant	<i>Silphium connatum</i>	Virginia Cuplant	Special Concern	Rockingham
Vascular Plant	<i>Silphium perfoliatum</i>	Northern Cuplant	Threatened	Stokes
Vascular Plant	<i>Solidago rigida</i> var. <i>glabrata</i>	Southeastern Bold Goldenrod	Rare	Rockingham
Vascular Plant	<i>Solidago ulmifolia</i>	Elm-leaf Goldenrod	Rare	Rockingham
Vascular Plant	<i>Sphenopholis intermedia</i>	Prairie Wedgescale	Watch List, Rare	Stokes
Vascular Plant	<i>Spiraea corymbosa</i>	Shinleaf Meadowsweet	Endangered	Stokes
Vascular Plant	<i>Stewartia ovata</i>	Mountain Camellia	Rare	Stokes
Vascular Plant	<i>Thermopsis fraxinifolia</i>	Ash-leaved Golden-banner	Special Concern	Stokes
Vascular Plant	<i>Thermopsis mollis</i>	Appalachian Golden-banner	Special Concern	Stokes

Vascular Plant	<i>Tradescantia virginiana</i>	Virginia Spiderwort	Threatened	Rockingham
Vascular Plant	<i>Trichostema brachiatum</i>	Glade Bluecurls	Endangered	Rockingham
Vascular Plant	<i>Tsuga canadensis</i>	Eastern Hemlock	Watch List, Rare	Stokes
Vascular Plant	<i>Tsuga caroliniana</i>	Carolina Hemlock	Watch List, Rare	Stokes
Vascular Plant	<i>Valerianella umbilicata</i>	Woodland Cornsalad	Watch List, Rare	Stokes
Vascular Plant	<i>Verbesina virginica</i> var. <i>virginica</i>	Frostweed	Watch List, Rare	Rockingham
Vascular Plant	<i>Viola tripartita</i>	Threearched Violet	Watch List, Rare	Stokes

Consent Decree

Appendix C

APPENDIX C
RESTORATION PROJECT SCOPES OF WORK

Restoration Project: Additional Mayo River Land Conservation

Project Description

To replace natural resource services allegedly lost as a result of the Release, the Settling Defendant shall acquire, or cause to be acquired on its behalf, floodplain and riverbank land along the Mayo River and convey, or cause to be conveyed on its behalf, ownership of the land to the State of North Carolina for conservation as part of North Carolina's Mayo River State Park.

Conservation of such property within the state park system of North Carolina provides ecological and recreational benefits: preserving high-quality habitat for threatened or rare terrestrial and aquatic species, and providing public access and recreational opportunities for anglers, hikers, paddlers, and other outdoor recreators.

After receiving ownership of a property, the State shall be responsible for stewardship of the property.

Performance Criteria

- The property (up to 64.403 acres) shall be identified at the sole discretion of, and approved by, the Trustees on the basis of benefits and values for riparian buffer and water quality protection, protection of habitat for rare or listed species, improved recreational access to the Mayo River, protection of property boundaries of the Mayo River State Park from encroachment, and expansion of the land base for future facility development and recreational opportunities at the parks.

- The property acquired shall be near or along the Mayo River from the Virginia-North Carolina state line extending downstream, including locations identified in the North Carolina Mayo River State Park Concept Plan.

- The property shall be conveyed to the State of North Carolina or agency

thereof.

- The Settling Defendant's acquisition of real property and conveyance of ownership to a State is subject to Paragraphs 10 through 12 of the Consent Decree.

Restoration Project: Public Boat Access

Project Description

Public responses to the Trustees' restoration scoping indicate that limited access in the Dan River basin impedes recreational use and enjoyment of the Dan River. To expand public boating opportunities within the Dan River watershed, the Settling Defendant shall construct a boat access facility within the Dan River watershed at one or more suitable locations identified at the sole discretion of, and approved by, the Trustees.

If determined by the Trustees as necessary for this Restoration Project, the Settling Defendant shall acquire, or cause to be acquired on its behalf, land for such facility or facilities. After completing construction of a facility, the Settling Defendant shall convey, or cause to be conveyed on its behalf, ownership of the property to the State of North Carolina or the Commonwealth of Virginia, depending on the location.

Performance Criteria

- The location(s) shall be identified at the sole discretion of, and approved by, the Trustees on the basis of benefits and values for improved recreational access to the Dan River watershed.
- The location(s) shall be located within the Dan River watershed along a river used for recreational boating purposes.
- If determined by the Trustees as necessary for this Restoration Project, the Settling Defendant shall acquire, or cause to be acquired on its behalf, land for the boat access facility. The Settling Defendant's acquisition of real property and conveyance of ownership to a State shall be subject to Paragraphs 10 through 12 of the Consent Decree.

- The boat launch may accommodate either motorized or non-motorized boats.
- The Trustees shall identify either (a) a maximum of one location suitable for motorized boat access or (b) a maximum of two locations, each suitable for non-motorized boat access.
- At each location, the Settling Defendant shall construct a boat access facility that provides, as determined by the Trustees, either motorized boat access or non-motorized boat access.
- If the location is in North Carolina on land acquired by the Settling Defendant or on its behalf: The Settling Defendant shall be responsible for constructing the boat access facility before ownership of the property is conveyed to North Carolina and as required under Paragraph 14 of the Consent Decree. After receiving ownership of the property with necessary improvements providing public boating access, North Carolina shall be responsible for maintaining the facility and public boating access thereafter.
- If the location is in Virginia on land acquired by the Settling Defendant or on its behalf: The Settling Defendant shall be responsible for constructing the boat access facility before ownership of the property is conveyed to Virginia and as required under Paragraph 15 of the Consent Decree. After receiving ownership of the property with necessary improvements providing public boating access, Virginia shall be responsible for maintaining the facility and public boating access thereafter.